

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

FDR (Emargent Work)

CIRCLE – R.W.D. works Circle, Kishangani

DIVISION – R.W.D. works Division , Kishangani-1

Name of Work :-	KUMAR TOLAI TO SIMALBARI TAK
Block :-	Bahadurganj
Length of Road:-	0.972 KM
Damage Length:-	0.393 KM
Estimated cost :-	Rs 897490.00

Year : 2021-22

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमंडल किशनगंज -1 अन्तर्गत बहादुरगंज प्रखंड के पथ . KUMAR TOLAI TO SIMALBARI TAK. (MMGSY) जो विभागीय Online Moritring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक- मु0अ0-4 (मु0) विविध कार्य-23-60 / 2020-1937 / पटना, दिनांक 07.07.2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में नदी/नदी उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु मोटेरेबल कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांकका Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटेरेबल कार्य में आवश्यकतानुसार Bomboo Pilling/Pitiching of E.C.Bag Filled With Local Sand/Local Sand Filling/Brick Bats का इस्तेमाल किया गया है। मोटेरेबल कार्य कराकर यातायात बहाल करा दिया गया है। निर्देशानुसार कराए गए कार्य की Geotagged Photo Realtime के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेत्तर कार्रवाई की जा सके।


25.08.21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा बहादुरगंज


15/11/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल बहादुरगंज


15/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल किशनगंज-1

Inspection Report for Flood Damage Work

1. Name of PIUs

: R.W.D Kishangang-1

2. Name Of Block / Road

: Kumarr Tolai to Simalbani Tak under Bahadurgang Block

A. For Road

1. Damage Location / Chainage

:

2. Damage Length

: - 0.393 KM

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

: Bamboo, Brick bats, Local sand Ec. bags

ii) Equipment / Tools Being Used In Restoration Works

: Tractor Bamboo Piling Machine

iii) Procedure Taken Up In Restoration Works

: Manually.

iv) Restored Length

: - 0.393 KM

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

) Material Being Used In Restoration

:

) Equipment / Tools Being Used in Restoration Works

:

i) Procedure Taken Up In Restoration Works

:

) Restored Length

:

Sati's factory,

12.04.22

Signature of JE / AE / EE

02.04.22

4/4/22

Signature

(Name Of Inspector)
कार्यपालक अभियन्ता
कार्य विभाग
कार्य प्रमण्डल, अररिया

ABSTRACT OF COST

Name of Work :-		KUMAR TOLAI TO SIMALBARI TAK
Block :-		Bahadurganj
Length of Road:-		0.972 KM
Damage Length:-		0.393 KM
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 773225.00
B	Add 12 % GST	Rs 92787.00
C	Add 1 % L. Cess	Rs 7732.00
D	Add S.Fee @ 10 % of Material Cost	Rs 23746.00
	Total Cost with GST, LC & S.Fee	Rs 897490.00


25-08-21
J.E/RWD
Bahadurganj


15/11/21
A.E/RWD
Bahadurganj


E.E/RWD
Kishanganj - I

Technically sanctioned for Rs. 897490/- (Eight lakh,
Ninty seven thousand, four hundred, Ninty) only.


Pallavi
06/04/22
E.O

अधीक्षक, अस्त्रियन्त्र
ग्रामीण कार्य विभाग
मध्यप्रदेश, विन्ध्यपुर

Detailed Estimate


[illegible]

Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
				1	1	12.00	0.30	0.50	1.80			
				1	1	7.00	0.50	0.60	2.10			
				1	1	8.00	0.70	0.70	3.92			
				1	1	13.00	0.30	0.70	2.73			
				1	1	74.00	0.70	0.60	31.08			
				1	1	25.00	0.70	0.80	14.00			
				1	1	30.00	0.60	0.70	12.60			
				1	1	22.00	0.80	1.00	17.60			
				1	1	4.00	0.70	2.00	5.60			
				1	1	6.00	2.20	2.20	29.04			
				1	1	5.00	1.00	1.00	5.00			
				1	2	39.00	0.70	0.70	38.22			
				1	1	30.00	0.80	0.60	14.40			
				1	1	31.00	0.70	0.70	15.19			
				1	1	39.00	0.70	0.90	24.57			
				1	2	28.00	0.95	0.90	47.88			
				1	1	20.00	1.00	1.00	20.00			
Total:-									285.73	Cum	514.43	146988.00
4	WRD	5.7.40	Brick bats Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction									
				1	1	12.00	0.30	0.30	1.08			
				1	1	7.00	0.50	0.30	1.05			
				1	1	8.00	0.70	0.30	1.68			
				1	1	13.00	0.30	0.30	1.17			
				1	1	74.00	0.70	0.45	23.31			
				1	1	25.00	0.70	0.45	7.88			
				1	1	30.00	0.60	0.30	5.40			
				1	1	22.00	0.80	0.30	5.28			
				1	1	4.00	0.70	0.30	0.84			
				1	1	6.00	2.20	0.30	3.96			
				1	1	5.00	1.00	0.30	1.50			
				1	2	39.00	0.70	0.45	24.57			
				1	1	30.00	0.80	0.45	10.80			
				1	1	31.00	0.70	0.30	6.51			
				1	1	39.00	0.70	0.45	12.29			
				1	2	28.00	0.95	0.30	15.96			
				1	1	20.00	1.00	0.30	6.00			
Total:-									129.28	Cum	2168.72	280372.00
5		5.7.53	Providing and filling empty cement bags Supply of new bag with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stitching on two line by approved nylon thread with stitching machine & generator, stacking the bags and placing with a lead of 150m including supply of nylon threads etc all complete as per approved design, specification and direction									
				1	1	12.00	0.45	0.80	4.32			
				1	1	7.00	0.45	0.90	2.84			

SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
			1	1	8.00	0.45	1.00	3.60			
			1	1	13.00	0.45	1.00	5.85			
			1	1	74.00	0.45	1.05	34.97			
			1	1	25.00	0.45	1.25	14.06			
			1	1	30.00	0.45	1.00	13.50			
			1	1	22.00	0.45	1.30	12.87			
			1	1	4.00	0.45	2.30	4.14			
			1	1	6.00	0.45	2.50	6.75			
			1	1	5.00	0.45	1.30	2.93			
			1	2	39.00	0.45	1.15	40.37			
			1	1	30.00	0.45	1.05	14.18			
			1	1	31.00	0.45	1.00	13.95			
			1	1	39.00	0.45	1.35	23.69			
			1	2	28.00	0.45	1.20	30.24			
			1	1	20.00	0.45	1.30	11.70			
Total:-								239.96	Cum		
@ 0.034 Cum each bag								7058	No.	38.03	268416.00
Total:-											773225.00


 25.08.21
 J.E/RWD
 Bahadurganj


 15/11/21
 A.E/RWD
 Bahadurganj


 E.E/RWD
 Kishanganj - I

ABSTRACT OF QUANTITY & COST

SI No	Item of Works	Quantity	Unit	Earth Work	Stone Materials			Brick Bats	Local Sand	Total
					26.5mm to 9.50mm	9.50mm to 4.75mm	4.75mm below			
1	Earth Work:-	0.00	Cum	0.000	-	-	-	-	-	
2	GSB (Gr.-II):-	0.00	Cum	-	0.000	0.000	0.000	-	-	
3	Brick Bats:-	129.28	Cum	-	-	-	-	155.136	-	
4	Local Sand Filling:-	285.73	Cum	-	-	-	-	-	285.730	
5	Providing & Filling Empty Cement Bags:-	7058.00	No.	-	-	-	-	-	239.972	
6	Providing & Filling Empty Cement Bags in Nylon Crate:-	0.00	No.	-	-	-	-	-	0.000	
		Total Quantity:-		0.000	0.000	0.000	0.000	155.136	525.702	
			Rate:-	Rs 34.78	Rs 285.35	Rs 285.35	Rs 285.35	Rs 1050.00	Rs 141.85	
		Total Amount:-		0.00	0.00	0.00	0.00	162893.00	74571.00	Rs 237464.00
								S.Fee@10% of M.Cost:-		Rs 23746.00


25.08.24
JE/RWD
Bahadurganj


15/11/24
AE/RWD
Bahadurganj


EE/RWD
Kishanganj - I