



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

6/12

DETAILED PROJECT REPORT FOR FDR

बिहार



DISTRICT : VAISHALI

BLOCK : MAHUA

ROAD NAME : Kanhauli bishanpur to shambhupatti

FLOOD DAMAGED ROAD

5

TOTAL LENGTH

: 3.100 KM

TOTAL PROJECT COST

: 2.93 3.15 LAKH

SUBMITTED BY
EXECUTIVE ENGINEER
RURAL WORKS DEPTT.
WORKS DIVISION
MAHUA

GENERAL ABSTRACT OF COST

Name of Road-Kanhauli bishanpur to shambhupatti
 District-Vaishali
 Block-Mahua
 Length(in KM)-3.10

Sl. No.	Item Of Work	Amount(in Rs)
	Earthwork	0
	Brick Bats	315087.99 293230.69 3.151
	Sand Filling	0
	Sub Total	315087.99 293230.69
	Grand Total (In Lacs)	Self 2.93 3.15

[Signature]
 22.11.21

[Signature]
 22/11/21
 JS

[Signature]
 22/11/21
 AC

... E.E. PWD (M) Circle Muz
 Letter No. 1179 Dated 01/10/2021
 Estimate has been verified by inspecting
 E.E. PWD. (M) Division Muzaffarpur

Technically Sanctioned for Rs. 3.15 lacs
 (Rs. Three lacs fifteen thousand) only
 (provisionally)

[Signature]
 30.12.21
 Superintending Engineer
 Rural Works Department
 Work Circle, Muzaffarpur

[Signature]
 30.12.21

Inspection Report for Flood Damage Work

Date :-

Name of P.U. :-

Name of Block Road :-

A. For Road: Kanhaul Bishampur to Chambaupatti

1. Damage Location Chainage :- 1900 - 1950, 2000 - 2100

2. Damage Length :- 100 mtr

3. Nature of Damage :- flood

4. Details of Restoration Works :-

Material being used in Restoration works:- Brk bat (152.618 cum)

Equipment's/Tools being used in Restoration works:- Tractor, Gravel loader

Procedure taken up in Restoration works:- Immediate repair for traffic

5. Restored Length :-

work found satisfactory

B. For Bridge:

1. Damage Location/Chainage :-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works :-

Material being used in Restoration works:-

Equipment's/Tools being used in Restoration works:-

Procedure taken up in Restoration works:-

5. Restored Length :-

N/A

Signature
15.12.21
of JE/AE/EE

Signature
15.12.21

Signature

(Name of Inspection)

प्रतिवेदन

कर्म का नाम - कन्हौली बिशनपुर से शंभुपट्टी

पथ में अप्रत्याशित बाढ़/अतिवृष्टि से क्षतिग्रस्त पथ में

आवश्यक धालू करने हेतु आपातकालीन मरम्मत कार्य।

प्रस्ताव - मकुआ
वित्तीय वर्ष - 2021-22
प्रकारित राशि - Rs. 2.43 लाख
3.15

प्रस्तुत प्राक्कलन जिसकी प्राक्कलित राशि 3.15
2.43 लाख है, कन्हौली बिशनपुर
से शंभुपट्टी प्रखण्ड मकुआ में यातायात बहाली हेतु आपातकालीन मरम्मत के
लिए तैयार किया गया है।

अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार पटना के पत्रांक 1539 दिनांक 13.11.21 द्वारा
विशेष गैर निर्देश के आलोक में उक्त पथ के क्षतिग्रस्त पथ में Brick Bats & Local Sand भरकर पथ को चालू
करने का प्रावधान किया गया है। प्राक्कलन वर्तमान धलू अनुमति दर पर तैयार किया गया है। इसकी
पटवोतर स्वीकृति अपेक्षित है। मकुआ में सड़क की डिट (प्लाया धरि संलग्न)

अभियंता
अभियंता

सहायक अभियंता
सहायक अभियंता

04.12.21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल

Sl No	SOR Sl.No	MORD Ref No.	Description	Unit	Quantity	Rate	Amount
1			Providing and Laying Brick Bats				
			Providing laying spreading and compacting Brick Bats including spreading in uniform thickness hand packing (manual means)		152.61		315073.00
			As per Appendix I	Cum	152.6175	964.90	245827.89
				Total	152.6175	1921.34	293220.69
2			Sand Filling				
		11.2	Filling in Foundation trenches as per drawing and technical specification clause 305.3.9				
				Cum	0		
				Total	0		
				Total			293230.69
							345887.99

22-11-21

3.151 lacs

Alfa

Alfa

AE.