



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

YEAR-2020-21

DETAILED PROJECT REPORT TEMPORARY RESTORATION WORK

DISTRICT :-

DARBHANGA

BLOCK :-

BAHADURPUR

ROAD NAME :

DALOR TO JALWAR

HEAD

FDR

YEAR-2021-22

TOTAL LENGTH OF ROAD

:

4.623

KM

DAMAGE LENGTH

:

0.082

KM

TOTAL COST OF PROJECT

:

0.752

LAKH

6.786

Executive Engineer
RWD Darbhanga-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected by Benipur

Name of Block/Road:- Daler to Jalwar

A. For Road

1. Damage Location Chainage:- 100 to 200 M

2. Damage Length :- 82 M

3. Nature of Damage :- Road crust chipped

4. Details of Restoration Works

i. Material being used in Restoration works:- Brine salt

ii. Equipment's /Tools being used in Restoration works:- J.C.B / tractor / labor

iii. Procedure taken up in Restoration works:-

iv. Restored Length:- 82 M
Laying of Brine salt with light ramming

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

N/A

Work found Satisfactory

Signature of JE/AE/EE



Signature

(Name of Inspection)

E.E. Benipur

GENERAL ABTRACT OF COST		
NAME OF ROAD :	DALOR TO JALWAR	
DISTRICT	DARBHANGA	
BLOCK	BAHADURPUR	
LENGTH OF ROAD (in Km)	4.623	
DAMAGED LENGTH (KM)	0.0824	
Sl. No.	DESCRIPTION	AMOUNT
1	Cost of Restoration	66573.193
2	GST @12%	7988.783
3	Labour cess @1%	665.732
4	Seigniorage fee	3426.24
5		8.986
6	Grand Total	78653.95
	Say(lacs)	0.786 0.752


Say 78654=00.


JE
RWD


AE
RWD


EE
RWD

कार्य पालक अभियंता बेनीपुर के जांच प्रतिवेदन के आधार पर
Technically sanctioned for Rs 78,654=00 (Rupees seventy
eight thousand six hundred fifty four only.)


अधिक्षण अभियंता
कार्य अंचल, दरभंगा
Abhinav
20/02/22

Detail Estimate For Motorable work of Road									
Name of road		Block			District		Division		Length(KM)
DALOR TO JALWAR		BAHADURPUR			DARBHANGA		DARBHANGA-I		4.623
Sl. No.	Description	Unit	Nos	LENGTH	Avg. width	Avg Hight	Qty	RATE	AMOUNT (in Rs.)
1	Labour and Placing Brick bats with Light raming including cost of brick bats by tractor	9-500m- 1000-3000m cum	2.00	30.00	3.48	0.15	31.32		
			1.00	3.20	0.30	0.40	0.38		
			1.00	1.50	0.45	0.75	0.51		
			1.00	1.30	1.40	0.10	0.18		
			1.00	1.40	1.00	0.10	0.14		
			1.00	2.20	0.30	0.20	0.13		
			1.00	5.00	0.30	0.20	0.30		
			1.00	2.00	0.30	0.20	0.12		
			1.00	6.00	0.20	0.10	0.12		
Total							33.20	2,004.96	66,573.19
DAMAGE LENGTH(M)				82.60					

JE
RWD

AE
RWD

EE
RWD

Verified & found correct

11/15-12-21
JE

Shahi
15/12/21
AE

3/12/21
EE Benipur