



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

YEAR-2020-21

DETAILED PROJECT REPORT

TEMPORARY RESTORATION WORK

DISTRICT :-

DARBHANGA

BLOCK :-

Hanumannagar

ROAD NAME :

BHAROUL TO UDHOPATTI

HEAD

FDR

YEAR-2021-22

TOTAL LENGTH OF ROAD

: 1.170

KM

DAMAGE LENGTH

: 0.006

KM

TOTAL COST OF PROJECT

: ~~0.382~~

LAKH

0.399

Executive Engineer
RWD Darbhanga-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected by Benipar

Name of Block/Road:- Bharaul to udhopatti

A. For Road

1. Damage Location Chainage:- 0 to 30 M

2. Damage Length :- 0.6 M

3. Nature of Damage :- Breach

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick Bats

ii. Equipment's /Tools being used in Restoration works:- JCB/Dozers/Labour

iii. Procedure taken up in Restoration works:- Laying of brick bats with light ramming

iv. Restored Length:-

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

Work found satisfactory.

Signature of JE/AE/EE

Signature
(Name of Inspection)
EE Benipar

GENERAL ABTRACT OF COST

GENERAL ABTRACT OF COST		
NAME OF ROAD :		BHAROUL TO UDHOPATTI
DISTRICT		DARBHANGA
BLOCK		HANUMANNAGAR
LENGTH OF ROAD (in Km)		1.170
DAMAGED LENGTH (KM)		0.006
Sl. No.	DESCRIPTION	AMOUNT
1	Cost of Restoration	33833.700
2	GST @12%	4060.044
3	Labour cess @1%	338.337
4	Seigniorage fee	1742.00 -8.986
5	Grand Total	39974.08 38241.067
6	Say(lacs)	0.399 -0.382

Say 39974 = 00

[Signature]

JE
RWD

[Signature] 6.11.21

AE
RWD

[Signature]

EE
RWD

कारिगलक आभियता केनीपुर के जॉय एलिमेंट्स के आधार पर

Technically sanctioned say 39,974 (thirty-nine thousand nine hundred ninety four only)

[Signature]
आधक्षण अभियता
कार्य अंचल, दरभंगा

Abhinav

26/02/22

Detail Estimate For Motorable work of Road									
Name of road		Block			District		Division		Length(KM)
BHAROUL TO UDHOPATTI		HANUMANNAGAR			DARBHANGA		DARBHANGA-I		1.17
Sl. No.	Description	Unit	Nos	LENGTH	Avg. width	Avg Hight	Qty	RATE	AMOUNT (in Rs.)
1	Labour and Placing Brick bats with	50-25cm cum	1.00	6.00	3.75	0.75	16.88		
Total							16.88	2,004.96	33,833.70
DAMAGE LENGTH(M)				0.01					

[Signature]
JE
RWD

[Signature]
AE
RWD

[Signature]
EE
RWD

checked by

[Signature]
10-12-2017

[Signature]

[Signature]
10/12/2017

[Signature]

[Signature]
10/12/17

[Signature]
B. S. Puro