



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FDR

ESTIMATE FOR MOTERABLE OF ROAD

YEAR - 2021-22

DISTRICT :- DARBHANGA BLOCK :- BAHERI

1.421

Total Cost of Project:- Rs. 2.17207 Lacs

Name of Raad :- Ujjain sukhan sah ke gha-se mahadalit tola Arjun Ram Ke Ghar Tak

Total Length :- 0.800 KM.

Effective Length :- 0.117 KM.

Inspection Report of Flood Damage work

ne of PIUs:- RWD Works Division, Darbhanga I

ne of Block/Road:- Baheri / Ujjain - Sukhan Sah ke Ghar se Mahadalit Kola Arjun
Ran ke khud tak

For Road

1. Damage Location Chainage:- 0 km to 8 km

2. Damage Length :- 0.117 km

3. Nature of Damage :- Surface Damage

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick Bats

ii. Equipment's / Tools being used in Restoration works:- JCB, Tractor, Labourers

iii. Procedure taken up in Restoration works:- Laying of Brick Bats with Light Ramming

iv. Restored Length:- 0.117 km

For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-


ii. Equipment's / Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

} N/A

WORK Found satisfactory



Signature of JE/AE/EE

Signature

(Name of Inspection)

FDR

DISTRICT :- DARBHANGA

BLOCK :- BAHERI

**Name of Raad :- Ujjain suktan sah ke gha se mahadalit tola
Arjun Ram Ke Ghar Tak**

**Length of the Road:- 0.800 KM.
Effective Length 0.117 KM.**

GENERAL ABSTRACT OF COST

No.	Item of Work	Amount (in Rs.)
1	Cost for restoration	120297.60 / 1,83,604.21
2	Add 12 % GST	14435.71 / 22,032.51
2	Add Seigniorage $60 \times 1032 \times 10\%$	6192.00 / 9,734.42
4	Add 1 % Labour Cess	1202.97 / 1,886.04
Total cost:-		142128.28 / 2,17,207.18

Say Rs. 142128/-


Junior Engineer
Baheri


Assistant Engineer
Baheri


Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता, बहरी के माँच प्रतिवेदन के आधार पर -

Technically sanctioned for Rs 142128/- (one
lacs forty two thousand one hundred twenty eight rupees)


अधिक्षण अभियंता
कार्य अंचल, दरभंगा
District Engineer

Detailed estimate for making moterable road.

of Raad :- Ujjain sukhani sah ke gha se mahadalit tola Arjun Ram Ke Ghar Tak
 - BAHERI
 CT :- DARBHANGA
 Works Division Darbhanga-1

Item	Unit	No.	Length (m)	Avg. Bre adth (m)	Avg. De pth / Height	Quantity	Rate	Amount
Labour and placing of brick bats with light raming including cost of brick bats by tractor	cum	From Ujjaina						
		0.000 KM to 0.800 KM.						
		1	30.00	3.00	0.250	22.500	13.500	
		2	30.00	2.75	0.300	49.500	33.000	
		1	27.00	2.50	0.290	19.575	13.500	
					Total	91.575	2004.96	183604.21

60.00

183604.21

120297.60

Junior Engineer
Baheri

Assistant Engineer
Baheri

Executive Engineer
R.W.D.(W) Division, Darbhanga-1

Verified as per SE, Darbhanga Lt 2326 (Bm) at 31/12/21 & cost of order 5/10

21/12/21

21/12/21
AG

21/12/21