

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected By Benipur

Name of Block/Road:- HAYAGHAT/ Anar PWD to Dalit Basti shobhnath
Patti Laxmipur Road

A. For Road

1. Damage Location Chainage:- 0 km to 2.560 km

2. Damage Length :- 194.60 m

3. Nature of Damage :- Surface Damage

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick Bats

ii. Equipment's /Tools being used in Restoration works:- JCB / Tractor / Labourers

iii. Procedure taken up in Restoration works:- laying of Brick Bats with light
iv. Restored Length:- 194.60 m Ramming

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

N/A

Work Found Satisfactory

Signature of JE/AE/EE

Signature

(Name of Inspection)

Benipur

ABSTRACT

Road Name- Temporary Restoration of Road from Anar PWD to Dalit Basti Shobhnath Patti Laxmipur

Block- HAYAGHAT


RWD (W) DIVISION DARBHANGA -1

Road Actual Length - 2.560 KM


Efected Road Length - 197.10 M. ^{194.60 M}


S.No.		UNIT	QUANTITY	RATE	AMOUNT (Rs)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .	CUM	66.815 70.072	2004.96	133961.20 140491
4	Total Amount				140491
	Add G.S.T. 12 %				16859
	Add 1 % Labor cess				1405
	Seigniorage Fee @1032.00/cum x0.10				7231
					165986

133961.20
16075.20
1340.20
6895.00
158271.20




J.E.

Work Section Hayaghat


A.E.
Work Sub-Division
Hayaghat


E.E.
RWD Darbhanga -1

कार्यपालक अभियंता बैनीपुर के जाँच प्रतिवेदन के आचार पर
Technically sanctioned for Rs. 158271=00 (Rupees one lakh
fifty Eight Thousand two hundred seventy one) only


Superintending Engineer
RWD, Works Circle, Darbhanga


Detailed Estimate for Temporary Restoration of Anar PWD to Dalit Basti Shobhnath Patti
Laxmipur road for the year 2021 -22.

Block - Hayaghat

R.W.D.[W] Division -Darbhanga -1

Total Restoration Length -197.10 M

Length -2.560 KM

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
1	Providing and filling bricks bats in ditches including cost of bricks bats and labour all complete job as per specification and direction of E/I .					
	Chainage in M					
	2	1	2.30 ✓	1.30 ✓	0.150 ✓	0.449
	6	1	4.00 ✓	2.50 ✓	0.150 ✓	1.500
		1	2.20 ✓	1.20 ✓	0.150 ✓	0.396
	12	1	2.60 ✓	1.30 ✓	0.150 ✓	0.507
	42	1	2.80 ✓	$(0.75+1.30)/2$	0.150 ✓	0.431
	47	1	0.60 ✓	0.60 ✓	0.100 ✓	0.036
	133	1	5.00 ✓	1.50 ✓	0.150 ✓	1.125
	155	1	1.90 ✓	1.10 ✓	0.100 ✓	0.209
	165	1	1.50 ✓	1.00 ✓	0.150 ✓	0.225
		1	1.20 ✓	1.10 ✓	0.150 ✓	0.198
	170	1	3.30 ✓	0.90 ✓	0.225 0.225	0.668 0.594
	260	1	3.45 ✓	1.20 ✓	0.225 ✓	0.932
		1	2.50 ✓	0.45 ✓	0.150 ✓	0.169
	295	1	18.30 ✓	1.10 ✓	0.150 ✓	3.020
		1	3.30 ✓	0.70 ✓	0.100 ✓	0.231
	381	1	5.10 ✓	$(0.90+2.50)/2$	0.250 ✓	2.168
		1	7.00 ✓	1.00 ✓	0.150 ✓	1.050
	393	1	9.00 ✓	1.00 ✓	0.225 ✓	2.025
	401	1	3.00 ✓	$(1.7+1.20)/2$	0.150 ✓	0.653
	445	1	3.50 ✓	3.75 ✓	0.300 ✓	3.938
	448	1	4.00 ✓	1.90 ✓	0.225 ✓	1.710
	458	1	5.80 ✓	1.50 ✓	0.225 ✓	1.958
		1	4.80 ✓	2.30 ✓	0.250 ✓	2.760
	477	1	3.80 ✓	3.75 ✓	0.250 ✓	3.563
	489	1	4.00 ✓	0.60 ✓	0.150 ✓	0.360
	505	1	2.20 ✓	1.50 ✓	0.150 ✓	0.495
		1	3.30 ✓	0.95 ✓	0.150 ✓	0.470
	519	1	10.55 ✓	1.30 ✓	0.225 ✓	3.086
	533	1	5.00 ✓	1.70 ✓	0.225 ✓	1.913

11/11/21

Block - Hayaghat

Total Restoration Length -197.10 M


R.W.D.(W) Division -Darbhanga -1

Length -2.560 KM

S.N.	item	No.	Length (M)	Width(M)	Depth (M)(AV)	Quantity (cum)
		1	3.60 ✓	0.70 ✓	0.225 ✓	0.567
	538	1	4.80 ✓	3.75 ✓	0.250 ✓	4.500
	543	1	2.60 ✓	1.10 ✓	0.150 ✓	0.429
	551	1	2.20 ✓	1.30 ✓	0.150 ✓	0.429
	552	1	12.20 ✓	1.20 ✓	0.200 ✓	2.928
	573	1	3.00 ✓	1.30 ✓	0.150 ✓	0.585
		1	3.00 ✓	0.70 ✓	0.150 ✓	0.315
	579	1	3.00 ✓	1.50 ✓	0.150 ✓	0.675
		1	2.00 ✓	0.60 ✓	0.150 ✓	0.180
	582	1	16.75 ✓	3.80 ✓	0.300 0.25 ✓	19.095 15.912
	603	1	7.15 ✓	0.70 ✓	0.200 ✓	1.001
	605	1	3.10 ✓	1.30 ✓	0.150 ✓	0.605
		1	1.50 ✓	1.00 ✓	0.150 ✓	0.225
	615	1	2.30 ✓	3.80 ✓	0.200 ✓	1.748
		1	3.50 ✓	(0.90+1.90)/2	0.100 ✓	0.490
	632	1	0.80 ✓	0.75 ✓	0.100 ✓	0.060
	Total Qty.					70.072

66.875 m


JE




EE

RWD(W) Division Darbhanga -1


checked by



11.12.2021



11.12.2021



11.12.21

Bangor