



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L067-KALHANABARI CHOWK TO BISWANPUR VIA JAIJAN (VR67)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 0	
DISTRICT	KATIHAR	
BLOCK	BALRAMPUR	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	0.000	KM
TOTAL COST OF F.D.R. PART - A	Rs. 2.958	Lacs
ADD G.S.T @ 12%	Rs. 0.355	Lacs
ADD Labour Cess @ 1%	Rs. 0.030	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.158	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 3.501	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल लाहौराई अन्तर्गत बलारामपुर..... प्रखंड के पथ L.6.7. KALHANBARI CHOWK to BISWANPUR VIA JAIJAN(.....) जो विभागीय Online Monitoring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-12/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 01.11.2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का गइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

28/11/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,

28/11/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,

28/11/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल,

28/11/21

Inspection Report for Flood damage work

Date:

1. Name of PIUs- EE. RWD. Barsai

2. Name of Block/Road- L067- Kathanabari chowk to Biswanpur via Jajar (VR 67)

A. For Road

1. Damage Location/Chainage : 0.00 to 0.450 km

2. Damage Length : 69 m

3. Nature of Damage

4. Details of Restoration : Shoulder and Crust

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

: Brick bats, bamboo, local sand, Empty cement bags

iii Procedure taken up in Restoration works

iv Restored Length : JCB, tractor etc

: 69 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature
Signature of JE/AE/EE

Signature
08/01/22
AE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L067-KALHANABARI CHOWK TO BISWANPUR VIA JAJAN (VR67)
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK BALRAMPUR
LENGTH OF ROAD (IN KM) 0.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	2.901
4	SAND BAGS	0.000
5	BAMBOO WORK	0.057
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		2.958
Add G.S.T. @ 12%		0.355
Add Labour Cess @ 1%		0.030
Add Surcharge Fee @ 10%		0.158
Total Cost of Restoration Work =		3.501

45 C Kumar
J.E. 8/11/22
RWD

28/11/21
J.E.
RWD

E.E.
RWD

Provisional Technical sanction of Rs 3.501 Lac
(Rupees Three Lac Fifty thousand one hundred) only

अधीक्षक अभियंता
ग्रामीण कार्य विभाग
काठ जंक्शन, पूर्णिया