



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L039-T01 TO LODHNA (VR39)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 3208	
DISTRICT	KATIHAR	
BLOCK	BARSOI	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	3.208	KM
TOTAL COST OF F.D.R. PART - A	Rs. 11.127	Lacs
ADD G.S.T @ 12%	Rs. 1.335	Lacs
ADD Labour Cess @ 1%	Rs. 0.111	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.563	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 13.136	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल बारसोई अन्तर्गत 01.11.21 प्रखंड के पथ Tel. (7) 31115 (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

30/11/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,

30/11/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,

30/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बारसोई

Inspection Report for Flood Damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- BGRSRI / To 1 to Ladang.

A. For Road

1. Damage Location/Chainage : 800m to 1900m

2. Damage Length : 100m

3. Nature of Damage : Flank, shoulder

4. Details of Restoration :

i Material being used in Restoration Brick, bely

ii Equipment/Tools being used in Restoration works: Baym, lero-

iii Procedure taken up in Restoration works :

iv Restored Length 100m :

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

Signature

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L039-T01 TO LODHNA (VR39)
 DISTRICT KATIHAR
 DIVISION BARSOI
 BLOCK BARSOI
 LENGTH OF ROAD (IN KM) 3.208

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	10.335
4	SAND BAGS	0.000
5	BAMBOO WORK	0.792
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		11.127
Add G.S.T. @ 12%		1.335
Add Labour Cess @ 1%		0.111
Add Seigniorage Fee @ 10%		0.563
Total Cost of Restoration Work =		13.136

30.11.21

J.E.
RWD

30.11.21

A.E.
RWD

30.11.21

E.E.
RWD

provisional Technically Sanctioned For Rs...13.136 Lacs.
 (Rupees.....Crore..thirteen
 lacs.....thirteen -
 thousands.Six.....Hundred) Only

अधीक्षक अभियंता
 ग्रामीण कार्य विभाग
 कार्य अंश, पूर्णिया