

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

RWD (Emargent Work)

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division , Kishanganj-1

Name of Work :-	Nazarpur Shishwari To L054
Block :-	Kochadhaman
Length of Road:-	0.650 KM
Damage Length:-	0.095 KM
Estimated cost :-	Rs 658265.00

Year : 2021-22

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य प्रमंडल, किशनगंज-1 अंतर्गत कोचाधामन प्रखंड के पथ "Nazarpur Shishwari To L054" जो विभागीय Online Monitoring Syatem MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Motorable हेतु बनाया गया है। इस कार्य को कराने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:- मु0अ0- 4 (मु0) विविध कार्य- 23 - 60 / 2020 - 1937 / पटना, दिनांक- 07.07.2021 से प्राप्त है। इस पत्र से Real time geo-tagged photograph को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक मेंनदी/नदी उपधार से आए बाढ़ के कारण इस पथ के Road way के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Motorable कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांकका Lat/Long के साथ लिया गया है। नेपाल तराई से निकलने वाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। Motorable कार्य में आवश्यकता अनुसार Bamboo Pilling / Pitching of E.C. Bags filled with local sand / Local sand filling / Brick bats का इस्तेमाल किया गया है। Motorable कार्य कराकर यातायात बहाल कर दिया गया है। निर्देशानुसार कराये गए कार्य का Geo-tagged photo real time के साथ MIS पर अपलोड है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथा शीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


30.10.21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा- कोचाधामन


30/10/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल- कोचाधामन


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, किशनगंज -1

Inspection Report for Flood Damage Work

1. Name of PIUs

: R.W.D Kishanganj

2. Name Of Block / Road

: Nazarpur Shishwari To LOSA under
Kochdhaman block.

A. For Road

1. Damage Location / Chainage

:

2. Damage Length

: - 0.095 KM

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration : Bamboo, Local sand, Brick Bats, Re bags.

ii) Equipment / Tools Being Used In Restoration Works : Tractor, Bamboo piling machine.

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

: - 0.095 KM

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

NA

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

:

Satisfactory


01.02.22
Signature of JE / AE / EE


01/02/22
Signature
कार्यपालक अभियन्ता
(Name of the Inspecting Officer)
कार्य प्रमण्डल, अखिरिया

ABSTRACT OF COST

Name of Work :-	Nazarpur Shishwari To L054	
Block :-	Kochadhaman	
Length of Road:-	0.650 KM	
Damage Length:-	0.095 KM	
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 567410.00
B	Add 12 % GST	Rs 68089.00
C	Add 1 % L. Cess	Rs 5674.00
D	Add S.Fee @ 10 % of Material Cost	Rs 17092.00
	Total Cost with GST, LC & S.Fee:-	Rs 658265.00


30-10-21

J.E/RWD
Kochadhaman


30/10/21

A.E/RWD
Kochadhaman



E.E/RWD
Kishanganj - I

Technically sanctioned too Rs. 658265/- (Six lakh, fifty eight thousand, two hundred sixty five) only.


06/04/22
E.O


अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

Detailed Estimate

[illegible]

Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
				1	1	25.00	0.45	1.65	18.56			
				1	1	10.00	0.45	1.65	7.43			
				1	1	30.00	0.90	2.10	56.70			
				1	1	30.00	0.90	2.10	56.70			
				Total:-					139.39	Cum		
				@ 0.034 Cum each bag					4100	No.	38.03	155923.00
				Total:-								567410.00


 30.10.21
 J.E/RWD
 Kochadhaman


 30/10/21
 A.E/RWD
 Kochadhaman


 E.E/RWD
 Kishanganj - I

ABSTRACT OF QUANTITY & COST

Sl No	Item of Works	Quantity	Unit	Earth Work	Stone Materials			Brick Bats	Local Sand	Total
					26.5mm to 9.50mm	9.50mm to 4.75mm	4.75mm below			
1	Earth Work:-	0.00	Cum	0.000	-	-	-	-	-	
2	GSB (Gr.-II):-	0.00	Cum	-	0.000	0.000	0.000	-	-	
3	Brick Bats:-	92.70	Cum	-	-	-	-	111.240	-	
4	Local Sand Filling:-	242.10	Cum	-	-	-	-	-	242.100	
5	Providing & Filling Empty Cement Bags:-	4100.00	No.	-	-	-	-	-	139.400	
6	Providing & Filling Empty Cement Bags in Nylon Crate:-	0.00	No.	-	-	-	-	-	0.000	
		Total Quantity:-		0.000	0.000	0.000	0.000	111.240	381.500	
		Rate:-		Rs 34.78	Rs 285.35	Rs 285.35	Rs 285.35	Rs 1050.00	Rs 141.85	
		Total Amount:-		0.00	0.00	0.00	0.00	116802.00	54116.00	Rs 170918.00
								S.Fee@10% of M.Cost:-		Rs 17092.00


 30.10.21
 JE/RWD
 Kochadhaman


 30/10/21
 AE/RWD
 Kochadhaman


 EE/RWD
 Kishanganj - I