

ग्रामीण कार्य विभाग

2021-2022

FLOOD DAMAGED REPORT



MOTORABLE OF REWATITH TO AJAMINAGAR

DISTRICT :- GOPALGANJ

DIVISION :- GOPALGANJ -2

BLOCK :- BAIKUNTHPUR

TOTAL LENGTH OF THE ROAD	:	9.700	KM
--------------------------	---	-------	----

DAMAGED LENGTH OF ROAD	:	0.070	KM
------------------------	---	-------	----

PART -A TOTAL COST OF INTIAL RECTIFICATION IN	:	2.06	Lacs
---	---	------	------

TOTAL SEIGNIORAGE FEE	:	0.003	Lacs
-----------------------	---	-------	------

TOTAL COST OF PROJECT	:	2.064	Lacs
-----------------------	---	-------	------

SUBMITTED By: EXECUTIVE ENGINEER

RWD (W) DIVISION GOPALGANJ-2

Name of work :-

MOTORABLE OF REWATITH TO AJAMINAGAR

Estimate Cost -

2.064 Lakhs

Total Length :-

9.700 Km


Description :- The Present estimate has been farmed under the supervision of Assistant Engineer in accordance with the order of Executive Engineer , RWD, Gopalganj 2. The part of above mentioned road has been damaged due to heavy rain/flood. And due to this damage the transportation has been obstructed. The immediate motorable work is necessary in public interest. Village will be benefitted by the completion of this motorable work.

In the estimate has been provision of repairing the damaged part of the road & making it motorable by filling brickbats. In the context of post flood scenario there is still the flow of water which prevails through the damaged part of the road.

In this estimate the rate of raw materials and labour wages has been prepared after the analysis of new rate. This estimate is as per specification . The estimate is devoted to technical and administrative acceptance.


J.E

A.E


E.E

Inspection Report For Flood Damage Work

Date:

1 Name of PIUs: Executive Engineer R.W.D W.D Gopalgau-2

2 Name of Block/Road: Baulkhatpur/Rawatth to Ajamanager

A For Road

1 Damage Location / Chainage:

1000 m to 1525 m

2 Damage Length: 70 m

3 Nature of Damage: Flood

4 Details of Restoration Works:

i. Material being used in Restoration Works: Bricks Bats

ii Equipments / Tools being used in Restoration Works: J.C.B tractor trolley

iii Procedure taken up in Restoration Works: yes

iv Restored Length: 70 m

B For Bridge

1 Damage Location / Chainage:

2 Damage Length:

3 Nature of Damage:

4 Details of Restoration Works:

i. Material being used in Restoration Works:

ii Equipments / Tools being used in Restoration Works:


iii Procedure taken up in Restoration Works:


iv Restored Length:

N/A


JE

AE


EE


25/3/22
Inspecting
Officer


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD :- MOTORABLE OF REWATITH TO AJAMINAGAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR
DIVISION :- GOPALGANJ -2
TOTAL LENGTH OF THE ROAD :- 9.700 KM
DAMAGED LENGTH OF ROAD :- 0.070 KM

SL.No	DESCRIPTION	AMOUNT	1 % Labour Cess	12 % GST	1 % Labour Cess & 12 % GST AMOUNT (LAKHS)
	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL				
1	BRICK BATS	1.82	0.018	0.219	2.06
	SUB TOTAL	1.82	0.018	0.219	2.06
	Total Seigniorage Fee				0.003
	TOTAL COST OF PROJECT IN LAKHS	1.82	0.018	0.219	2.064


21/12/21
Junior Engineer

Asstt. Engineer


21/12/21
Executive Engineer

FLOOD DAMAGED REPORT

GENERAL ABSTRACT OF COST

NAME OF ROAD :- MOTORABLE OF REWATITH TO AJAMINAGAR
DISTRICT :- GOPALGANJ
BLOCK :- BAIKUNTHPUR
DIVISION :- GOPALGANJ -2
TOTAL LENGTH OF THI :- 9.700 KM
DAMAGED LENGTH OF :- 0.070 KM

SL.No	Item of Work	AMOUNT
A	INITIAL RECTIFICATION INCLUDING SURFACE RENEWAL	2.06
B	Total Seigniorage Fee	0.003
	TOTAL	2.064

[Signature]
21/11/22

Junior Engineer

ASSTT. Engineer

[Signature]
21/11/22
Asstt. Engineer

F.D.R. Technically sanctioned for Rs 2.064 lacs (Rupees Two lacs
812 Thousand & Four Hundred) only

[Signature]
22/04/22
Superintending Engineer
R.W.D. Work, Circle, Siwan

[Signature]
22/04/22
u

Name of Road :- MOTORABLE OF REWATITH TO AJAMINAGAR

S.L No	SBD S.L No	MORD Ref No	DESCRIPTION	Unit	Quantity	Rate	Amount In Rs	Total Material Qty required (Cum)	Total Amount	Add 10 % Seigniorage Fee
--------	------------	-------------	-------------	------	----------	------	--------------	-----------------------------------	--------------	--------------------------

Providing Brick bats including spreading laying hand packing and compacting with C.I

Taking Out put = 2.832

Material

III) Local Sand

Cost for 300 cum = A

Rate per cum = (A) / 2.832

Cum	0.63	141.85	89.37
			89.37
			31.56
			31.56

Total Seigniorage Fee 328.11

24/12/17

21/12/17