



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

KATAR TO SIKARPUR VIA PAHARPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2340	
DISTRICT	KATIHAR	
BLOCK	KADWA	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	2.340	KM
TOTAL COST OF F.D.R. PART - A	Rs. 27.579	Lacs
ADD G.S.T @ 12%	Rs. 3.309	Lacs
ADD Labour Cess @ 1%	Rs. 0.276	Lacs
ADD Seigniorage Fee @ 10%	Rs. 1.185	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 32.349	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

Inspection Report for Flood damage work

Date:

1. Name of PIUs- E.E. R.W.D. Barsoi

2. Name of Block/Road- Katar to Sikarpur VIA Paharpur.

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 190.7 Mt.

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works

iii Procedure taken up in Restoration works

iv Restored Length

: Bamboo piling, Sand Bag, Borab Borab
J.C.B. etc
190.7 Mt.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works

iii Procedure taken up in Restoration works

iv Restored Length

MW
8/1/22
Signature of JE/AE/EE


Signature

(Name of Inspector)

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल पटना अन्तर्गत कृ. ६०१ प्रखंड पथ (.....) जो राष्ट्रीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य भाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक- /10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के डबे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से कलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का इल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बेट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, .../११/२१.....


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, .../११/२१.....

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, .../११/२१.....

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD.

NAME OF ROAD : KATAR TO SIKARPUR VIA PAHARPUR
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK KADWA
LENGTH OF ROAD (IN KM) 2.340


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	4.001
2	HUME PIPE	0.000
3	BRICK BATS	21.072
4	SAND BAGS	0.000
5	BAMBOO WORK	2.114
6	STEEL DRUM SHEET	0.392
TOTAL COST OF PROJECT =		27.579
Add G.S.T. @ 12%		3.309
Add Labour Cess @ 1%		0.276
Add Seigniorage Fee @ 10%		1.185
Total Cost of Restoration Work =		32.349


J.E.
RWD


A.E.
RWD


E.E.
RWD

Provisional technically Sanctioned for Rs:- 32.349 (Rs:- Thirty two Lacs thirty four thousand nine hundred Only)


अधीक्षक अभियंता
ग्रामीण कार्य विभाग
कार्ड अफिस, पूर्णिया