



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

DHACHANA RAILWAY LINE TO BALUPARA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 9300	
DISTRICT	KATIHAR	
BLOCK	BARSOI	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	9.300	KM
TOTAL COST OF F.D.R. PART - A	Rs. 19.751	Lacs
ADD G.S.T @ 12%	Rs. 2.370	Lacs
ADD Labour Cess @ 1%	Rs. 0.198	Lacs
ADD Seigniorage Fee @ 10%	Rs. 1.025	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 23.344	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

Inspection Report for Flood damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- **BARSOI**

A. For Road : **DHACHANA RLY. LINE TO BALUPARA**

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

: 376.90 Mts.

: Shoulder and cryst

: Brick Bat, Sand Bag, Bamboo Work

: Brick Bat, L/Sand, Bamboo and Empty cement Bag.

: JCB and Tractor.

: Manually.

: 376.90 Mts.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature


(Name of Inspector)


प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल बारसोई अन्तर्गत बारसोई प्रखंड के पथ CHACHANA RAILWAY LINE TO BALUPARA (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, बारसोई.....



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बारसोई

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : DHACHANA RAILWAY LINE TO BALUPARA
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK BARSOI
LENGTH OF ROAD (IN KM) 9.300

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	18.639
4	SAND BAGS	0.087
5	BAMBOO WORK	1.025
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		19.751
Add G.S.T. @ 12%		2.370
Add Labour Cess @ 1%		0.198
Add Seigniorage Fee @ 10%		1.025
Total Cost of Restoration Work =		23.344


J.E.
RWD 30-XI-09/1


A.E.
RWD 30-11-21


E.E.
RWD 30/11/21

provisional Technically Sanctioned For Rs. 23.344 Lacs.
(Rupees Crore Twenty three
lacs thirty four -
thousands four Hundred) Only


अधीक्षक अभियंता
राज्यीय कार्य विभाग
मुख्य अंश, प्रविष्ट