



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

PLAN HEAD- FDR YEAR 2021-22

DISTRICT :- WEST CHAMPARAN
BLOCK :- Majhaulia

Estimate for Repair of Road breaches
(Damaged by Flood) for Motorability in
SARISWA To MOHCHI BANKATWA PATH

LENGTH OF ROAD (in Km)- 2.6 KM

ESTIMATED COST -	1.970	Lacs
------------------	-------	------


SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BETTIAH

घोषणा-पत्र

1. इस प्राक्कलन को असंबद्ध कार्यपालक अभियन्ता से जाँच करा ली गयी है।
2. अस्थायी पुनर्स्थापन के सामग्री का समायोजन स्थायी पुनर्स्थापन के प्राक्कलन में कर ली गयी है।



सहायक अभियन्ता / कनीय अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया।


25.11.21

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2

पत्रांक-.....३५७...../ बगहा-2, दिनांक 22/11/2021

प्रेषक:-

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बगहा-2

सेवा में,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, बेतिया।

विषय :- कार्य प्रमंडल, बेतिया में वर्ष 2021 के बाढ़ में क्षतिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जाँच के संबंध में।

प्रसंग:- भवदीय पत्रांक-1325/बेतिया, दिनांक-14.11.2021 एवम् अभियन्ता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-मु0अ0-4(मु0) विविध (कार्य)-23-291 /2019-4589, दिनांक-13.11.2021।

महाशय,

उपर्युक्त विषयक एवम् प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल, बेतिया द्वारा उपलब्ध कराये गये मोटरेबुल पथों की सूची में अंकित पथों का अधोहस्ताक्षरी द्वारा सहायक अभियन्ता के साथ निरीक्षण किया गया। निरीक्षण के दौरान कार्य प्रमंडल, बेतिया द्वारा प्रतिवेदित सभी पथों पर कार्य कराया गया है एवम् यातायात चालु है।

सादर सूचनार्थ एवम् अग्रेत्तर कार्रवाई हेतु समर्पित।

अनु0- निरीक्षण किये गये पथों की सूची।

विश्वासभाजन,

Deewan
25.11.2021

सहायक अभियन्ता
ग्रा0का0वि0, का0प्र0, बगहा-2

कार्यपालक अभियन्ता
ग्रा0का0वि0, का0प्र0, बगहा-2

FDR List 2021 (Temporary Restoration)

Block Name	Name of Road	Length of Road (KM)	Amount (in Lac)
Majhauria	PMGSY to Shekh Toli		
Majhauria	Narayanpur - Parsa	2.25	2.282
Majhauria	Parsa Mauje Harizan Tola to Parsa Mauje Emiliyapur	1.29	8.556
Majhauria	Nanosati Jagdishpur Jane wali road to kusheswar sthan jane wali road	3	19.228
Majhauria	Sariswa to Mohchhi Bankatwa Path	2.43	13.566
Majhauria	L057-L056 Sekh Toli to Malah Toli (TRACK57)	2.6	1.97
Majhauria	Bin Toli to Nuniya Tola	2.1	3.033
Majhauria	L073-T02 to Gudra (TRACK73)	2.58	3.102
Majhauria	T03 - DIANGA TOLI	4.55	41.522
Majhauria	Turha Toli to Lala Tola	2.5	6.9
Majhauria	MANJHAULIA JAGDISHPUR ROAD - TOLA JAGARNATHPUR	1.295	6.719
Majhauria	Barwa - Bhagari	6.24	8.95
Majhauria	MNP Road Naika Tola to Mathiya Writ	4.648	33.465
Majhauria	L045 - World Bank Road to Badhiya (TRACK45)	1.65	1.195
Majhauria	L074-L041 to Ahir Tola (TRACK74)	2.65	6.162
Majhauria	L106-PMGSY to Bin Toli (TRACK106)	4.75	5.755
Majhauria	Harpur to T01 Harpur Chauk	1.5	3.387
Majhauria	HARPUR CHOWK to HARPUR PRIMARY SCHOOL	2.84	2.537
Majhauria	Sariswa Dhodha to Turha Toli	2.83	3.551
Majhauria	Sariswa PWD to Manjahi Tola (Chanayan Bandh)	2.08	4.886
Majhauria	PMGSY to Dhankutwa	1.43	2.04
Majhauria	L047 to Jagamb Tola	1.12	4.94
Majhauria	Mushar Toli to Koeri Tola	1.585	1.4
Majhauria	Bakulahar to Bankat	0.9	1.87
Majhauria	Mahanwa - Parsa Tola	1.815	0.612
Majhauria	Mahanwa rampur bakulia tola	10.22	2.707
Majhauria	Baghamberpur - Semraghat	4	49.934
Majhauria	Sarishava market to MR Road FDR	2	26.952
Majhauria	Bettiah Motihari PWD Road - Kakaukatia	1.2	17.841
Bettiah	DAIRY FARM - KODA BELDARI	4.635	4.432
Bettiah	RLY GUMATI - BANU CHHAPRA	1.175	4.503
Bettiah	L024-T01 Gonauli to Dharampur (TRACK24)	1.686	5.04
Bettiah	SARISWA ROAD - SINGHA CHHAPRA	1.275	12.21
Bettiah	PWD ROAD ITI to MUSHI TOLA BHAYA SARSWATI NAGAR	1.489	6.113
Bettiah	PMGSY Road Ke Bagar Patel ke Ghar To Sariya Tola	1.335	7.611
Bettiah	Ramjanki Mandir to new panitanki	2.1	12.967
Bettiah	ARERAJ PWD - LALA SARIYAN	2	11.011
Bettiah	Bettiah Areraj ward no7 to purwi kargahiya	2.02	3.085
Bettiah	L023-Gonauli to Khal Tola ,Mushartoli (TRACK23)	1.4	2.542
Bettiah	PMGSY Nimiya Chowk To Koiri Tola	3	4.514
Bettiah	Repair of road from Betiya Areraj Pitch road to Warwat Sewa Motihari Pitch road	1.65	8.124
Bettiah		2.25	3.002

Executive Engineer
RWD (W). Div.-Bagaha-2

GENERAL ABSTRACT OF COST

ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR
MOTORIBILITY IN SARISWA TO MOHICHI BANKATWA PATH

DISTRICT - WEST CHAMPARAN

DIVISION - BETTIAH


BLOCK - Majhauria

LENGTH OF ROAD (in Km)- 2.6 KM

SL. No.	Item of Work	Amount
1	EARTH WORK :	₹ 0.00
2	BRICK BATS :	₹ 1,61,889.57
3	HUME PIPE :	₹ 0.00
4	COST OF RESTORATION :	₹ 1,61,889.57
5	ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST :	₹ 14,049.00
6	ADD LABOUR CESS @ 1% :	₹ 1,618.90
7	ADD GST @ 12% :	₹ 19,426.75
8	TOTAL COST OF RESTORATION OF ROAD :	₹ 1,96,984.21

Say Rs.

197000 Lacs


Junior Engineer


Asstt. Engineer


Executive Engineer

*Technically ~~approved~~ sanctioned for amount Rs. 1.970 lacs.
(₹ one lac ninety seven thousand ~~thousand~~ only.)*


Superintendent Engineer
Rural Works Department
Works Circle, Bettiah
Govt. of Bihar


Superintendent Engineer
Rural Works Department
Works Circle, Bettiah
Govt. of Bihar

of Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in SARISWA To MOHCHI BANKATWA PATH

FDR

Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
Providing and Labour for laying dry graded Brick Bats including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum	As Per Appendix I				75.57	2142.53	161910.99
Providing and laying 1000 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	M	As Per Appendix II				0.000	0.00	0.00
Providing and laying 600 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	M	0.00				0.000	0.00	0.00
EARTH WORK - Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5	Nos.	0				0.000	0.00	0.00
TOTAL (in Re.)								161889.57


5-11-21
Junior Engineer,
Rural Works Department,
Works Section, Majhauria


5/11/21
Assistant Engineer,
Rural Works Department
Works Sub Division, Majhauria


Executive Engineer,
Rural Works Department,
Works Division, BETTIAH