

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



**Name of Work:-Pupri to Choraut.
Block:- Pupri.**

F.D.R

Rs.733220.00 498452.00


Year-2021-22

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

1	निरीक्षी पदाधिकारी का नाम एवं पदनाम:-	ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	22-12-2021
3	पथ का नाम (शीर्ष के साथ)	Pupri To choraut.
4	पथ की लम्बाई	6.00 Km
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	पुपरी।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	All Mesurment are attached in estimate Qty of Brick Bats :- 230.0544 m³ Qty of Rubbish:- 57.5136 m³ Total Qty :- 287.5680 m³ Entered in MB No:- 2651 Page No:- 3
11	अस्थायी पुर्नस्थापन में किस-किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	संतोष पट्ट


 निरीक्षी पदाधिकारी का हस्ताक्षर
 पदनाम सहित

DETAILED ESTIMATE FOR F.D.R

General Abstract of Cost

Name of Road:-Pupri to Choraut.

Length of Road:-6.00 Km

Block:-Pupri


District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	624625.00
2	Labour cess @1%	6246.25
3	GST @12%	74955.00
4	Seigniorage Fee @ 10%	27393.73
5	Total Cost of Road Repair	733219.98

Say Rs. ~~733220.00~~

498452.00



JE


AE


EE

अभियंता प्रमुख ग्रामीण कार्य विभाग के पत्रांक-4849 दिनांक-07/12/2021
के आदेशानुसार प्रशासनिक स्वीकृति के प्रत्याशा में औपबंधित तकनीकी
स्वीकृति प्रदान की जा रही हैं। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त
पुनः तकनीकी स्वीकृति प्रदान की जायेगी।
औपबंधित तकनीकी स्वीकृति रुपये 498452.00 (Four Lacs Ninety Eight thousand

fifty two) only की प्रदान की जाती है।


अधीक्षक अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, सीतामढ़ी

Schedule of Quantity

Name of Road:-Pupri to Choraut.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	488.11	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	287.5680			0.00
	Less 20% for Voids	57.5136			
		230.0544	Cum	2105.01	484266.813
3	Single bamboo paiasiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	140.4	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stiching with sutall etc. do.....do.....all complete job as per specification and direction of E/I. (including Royalty and all Taxes)	0.00	no.	9.63	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	15.00	m	3400.00	51000.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	0.00	m	850.00	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and direction of E/I.				
	Taking 20% of Brick Qty for Rabbish	57.5136	Cum	1553.68	89357.73

Total

Say

~~624624.54~~

~~624625.00~~

498452.00

JE

AE

Details of Measurement of ditches filled by brick bats and rabbish

Name of Road:-Pupri to Choraut.

	Nos.	L	W		H		VOLUME
CH 800 M	1	3.50	1.500		0.200		1.0500
	1	3.20	3.500		0.300		3.3600
	1	2.00	1.800		0.200		0.7200
	1	2.30	1.400		0.200		0.6440
CH 1800 M	1	6.00	2.000		0.200		2.4000
Near Pound	1	13.00	2.700		0.250		8.7750
	1	21.50	4.100		0.450		16.9490
	1	9.00	1.500		0.200		2.7000
CH 3000 to 3500 M	1	4.50	3.000		0.250		3.3750
	1	4.00	3.400		0.300		4.0800
	2	2.50	1.500		0.250		1.8750
	1	3.00	1.900		0.200		1.1400
CH 4500 M	1	2.50	1.400		0.250		0.8750
	1	4.50	4.000		0.250	Av	4.5000
	1	2.50	1.800		0.250		1.1250
	1	4.00	2.250		0.200		1.8000
Link Road Madhuni to Parsauni	1	8.00	3.000		0.250		6.0000
	1	30.00	3.250		0.300		29.2500
(in River bank)	1	11.00	5.000		0.300		16.5000
(in River bank)	1	30.00	5.700	Av	0.900		153.9000
	1	14.00	3.500		0.300		14.7000
Near Baijnath Mahto House	1	26.50	3.000		0.300		23.8500
					Total		299.5680
					Less for Pipe		12.0000
					Total (in Cum)		287.5680
Laying Hume Pipe of 1000 mm dia	6	2.5	0		0		15.00
Laying Hume Pipe of 600 mm dia		0	0		0		0.00
Cement Bage							

[Signature]
5/11/21

JE

[Signature]
5/11/21

AE

[Signature]
5/11/21

EE