



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

YEAR-2020-21

DETAILED PROJECT REPORT

TEMPORARY RESTORATION WORK

DISTRICT :-

DARBHANGA

BLOCK :-

Hanumannagar

ROAD NAME :

TARALAH TO SINUARA TANTI TOL

HEAD

FDR

YEAR-2021-22

TOTAL LENGTH OF ROAD

:

2.793

KM

DAMAGE LENGTH

:

0.023

KM

TOTAL COST OF PROJECT

:

0.269

LAKH

0.28087

Executive Engineer
RWD Darbhanga-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga1 Inspected by Benipur

Name of Block/Road:- Taralahi to Sinuara Tanti Tola

A. For Road

1. Damage Location Chainage:- 600 m to 900 m

2. Damage Length :- 20 m

3. Nature of Damage :- Breach.

4. Details of Restoration Works

i. Material being used in Restoration works:-

Rock balt

ii. Equipment's /Tools being used in Restoration works:-

3CB/Tractor/ Lorry

iii. Procedure taken up in Restoration works:-

iv. Restored Length:- 20 m

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

N/A

Work found satisfactory.

Signature of JE/AE/EE

Signature

(Name of Inspection)

E.E Benipur

GENERAL ABTRACT OF COST

NAME OF ROAD :		TARALAH TO SINUARA TANTI TOL	
DISTRICT		DARBHANGA	
BLOCK		HANUMANNAGAR	
LENGTH OF ROAD (in Km)		2.793	
DAMAGED LENGTH (KM)		0.0229	
Sl. No.	DESCRIPTION	AMOUNT	
		23772.811	
1	Cost of Restoration	2852.737	
2	GST @12%	237.728	
3	Labour cess @1%	1224.00 8.986	
4	Seigniorage fee	28087.00 26872.262	
5	Grand Total	0.28087 0.269	
6	Say(lacs)	28087.00 26872.262	

say 28,087=00

JE
RWD

AE
RWD

EE
RWD

कार्यक्रम अमियता वेनीपुर के लॉज प्रविष्टि के आधार पर
Technically sanctioned. say 28,087 (Rs. Twenty
Eight thousand- Eighty seven only)

अधिक्षण अमियता
कार्य अंचल, दरभंगा
Abhinav
26/12/20

Detail Estimate For Motorable work of Road

Detail Estimate For Motorable work of Road									
Name of road		Block			District		Division		Length(KM)
TARALAH TO SINUARA TANTI TOL		HANUMANNAGAR			DARBHANGA		DARBHANGA-I		2.793
Sr. No.	Description	Unit	Nos	LENGTH	Avg. width	Avg Hight	Qty	RATE	AMOUNT (in Rs.)
1	Labour and Placing Brick bats with Light raming including cost of brick bats by tractor	cum	1.00	1.50	0.80	0.15	0.18		
			1.00	1.50	1.00	0.15	0.23		
			1.00	1.60	1.00	0.15	0.24		
			1.00	0.80	0.80	0.80	0.51		
			1.00	11.00	2.50	0.25	6.88		
			1.00	3.50	3.00	0.25	2.63		
			1.00	3.00	2.00	0.20	1.20		
							Total		11.86
DAMAGE LENGTH(M)				0.02					

[Signature]
JE
RWD

[Signature]
AE
RWD

[Signature]
EE
RWD

Checked by *[Signature]*

[Signature]
10/12/2024

[Signature]

[Signature]
10/12/2024

[Signature]

[Signature]
10/12/24
[Signature]
Beedpur