



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

PURAB TOLA SEKHPURA TO PMGSY ROAD

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1300	
DISTRICT	KATIHAR	
BLOCK	KADWA	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	1.300	KM
TOTAL COST OF F.D.R. PART - A	Rs. 12.364	Lacs
ADD G.S.T @ 12%	Rs. 1.484	Lacs
ADD Labour Cess @ 1%	Rs. 0.124	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.652	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 14.624	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

Inspection Report for Flood damage work

Date:

1. Name of PIUs-

EE, RWD, Barsoi

2. Name of Block/Road-

Kadwa, Purab Tola Sekhpura to Pmasy Road.

A. For Road

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

153.70 mt

bamboo piling, Bricks bats etc

JCB

153.70 mt

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature


(Name of Inspector)

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल आराखड़ा अन्तर्गत कदवा प्रखंड के पथ (.....) जो विभागीय Online Monitoring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपध्वर से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।


प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, कदवा.....

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, कदवा.....

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, आराखड़ा.....

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PURAB TOLA SEKHPURA TO PMGSY ROAD
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK KADWA
LENGTH OF ROAD (IN KM) 1.300

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BATS	10.503
4	SAND BAGS	0.685
5	BAMBOO WORK	1.176
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		12.364
Add G.S.T. @ 12%		1.484
Add Labour Cess @ 1%		0.124
Add Seigniorage Fee @ 10%		0.652
Total Cost of Restoration Work =		14.624

MW
30/11/21
J.E.
RWD

2/11/21
RWD

30/11/21
E.E.
RWD

Provisional technically Sanctioned for Rs:- 14.624 (Rs:- Fourteen
Lacs Sixty two thousand four hundred only)

आजारा कार्यालय
कार्य प्रमुख, प्रमिता