

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

CIRCLE – R.W.D. works Circle, Kishanganj

DIVISION – R.W.D. works Division , Kishanganj-1

Name of Work :- Panchgachhi Road to L029 Kharra Belbari ~~1st~~

Block :- Terhagachh

Length of Road:-

Damage Length:-

Estimated cost :- Rs 15,44,972 = 60 .

Year : 2021-22

ग्रामीण कार्य विभाग
बिहार, सरकार

पत्रांक - मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

पटना, दिनांक 07/07/2021

प्रेषक,

पंकज कुमार पाल (भा0प0से0)
सचिव

सेवा में,

सभी कार्यपालक अभियंता
ग्रामीण कार्य विभाग,

विषय- बाढ़ अतिवृष्टि से क्षतिग्रस्त पथों/पुलियों को यातायात लायक (Motorable) करने के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में निदेश दिया जाता है कि प्रमंडल अन्तर्गत सभी अभियंता बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों का शत प्रतिशत निरीक्षण करेंगे। पथों/पुलियों के क्षतिग्रस्त भाग से पानी उतरते ही उसे यातायात लायक बनाने की कारवाई एवं Motorable किये जाने से पहले तथा Motorable कार्य के बाद का Real time, Geo tagged photographs को MIS पर तत्क्षण अपलोड किया जाना सुनिश्चित करेंगे। इन कार्यों को कराने हेतु कार्यपालक अभियंता पूर्ण रूप से जिम्मेवार होंगे। कार्य न कराने की स्थिति में उनके विरुद्ध अनुशासनिक कार्रवाई की बाध्यता होगी।

विश्वासभाजन

(पंकज कुमार पाल)

सचिव

ज्ञापांक- मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी अधीक्षण अभियंता को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। साथ ही उन्हें निदेश दिया जाता है कि वे लगातार अनुश्रवण एवं निरीक्षण करते हुए क्षतिग्रस्त भाग को अतिशीघ्र यातायात लायक बनवाने की कारवाई सुनिश्चित करेंगे।

सचिव

ज्ञापांक-मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

पटना, दिनांक 07/7/2021

प्रतिलिपि:-सभी मुख्य अभियंता, ग्रामीण कार्य विभाग को सूचनार्थ एवं लगातार अनुश्रवण करने हेतु प्रेषित।

सचिव

Inspection Report for Flood Damage Work

Date:

1. Name of PIUs - Executive Eng. RWD works division Kishanganagar-1.
2. Name of Block/Road - Terhagachh / panchgachhi road to Loda Khanna - belbari.

A. For Road

1. Damage Location/Chainage :
2. Damage Length : 257 m.
3. Nature of Damage : Surface and flank damage.
4. Details of Restoration Works :
 - i. Material being used in Restoration works : Local sand, brick bats -
 - ii. Equipments/Tools being used in Restoration works : Grader.
 - iii. Procedure taken up in Restoration works : manual.
 - iv. Restored Length : 257 m

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length : } N.A.
3. Nature of Damage :
4. Details of Restoration Works :
 - i. Material being used in Restoration works :
 - ii. Equipments/Tools being used in Restoration works :
 - iii. Procedure taken up in Restoration works :
 - iv. Restored Length :

Satisfactory.

24/12/22
Signature of JE/AE/EE

24/12/22
Signature
कार्यपालक अभियन्ता
(Name) प्रमाण कार्य विभाग
कार्य प्रमण्डल, अररिया

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमंडल किशनगंज -1 अन्तर्गत प्रखंड के पथ Panchgachhi Road to L.M. Khanna Belhari () जो गीय Online Monitoring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त होने के कारण यातायात लायक Motorable हेतु बनाया गया है। इस कार्य को का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक- मु0अ0-4 (मु0) ध कार्य-23-60/2020-1937/पटना, दिनांक 07.07.2021 से प्राप्त है। इस पत्र Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में नदी/नदी उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु मोटेरेबल कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांक का Lat/Long साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस में कटाव की स्थिति बनी। मोटेरेबल कार्य में आवश्यकतानुसार Bomboosing/Pitching of E.C.Bag Filled With Local Sand/Local Sand Filling/Brick ts का इस्तेमाल किया गया है। मोटेरेबल कार्य कराकर यातायात बहाल करा दिया है। निर्देशानुसार कराए गए कार्य की Geotagged Photo Realtime के साथ MIS पर उद्धृत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में मुक्त दर अद्यतन है

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेत्तर कार्रवाई की जा सके।

13/9/2021
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा

13.09.2021
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल किशनगंज-1

Abstract of Cost

Name of Work:- Panchgachhi Road to L.029 Kharra Belhari

Block :- Terhagachh

District:- Kishanganj

S.L No.	Name of cutting of roads	Amount (In Rs.)
1	1st Cutting	Rs 10,61,657 = 00
2	2nd Cutting	Rs 483315.00
	Total Cost=	Rs 15,44,972 = 00

Soni
12/9/24
J.E
RWD
Terhagachh

209
A.E 13.07.2024
R.W.D
Terhagachh

CTM
E.E
RWD
Kishanganj-I


Technically Sanctioned for Rs:- 15,44,972 = 00 (Rs:- fifteen lacs forty four thousand nine hundred seventy two) only.

Pallavi
06/04/22
E.O

Bh
अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

ABSTRACT OF COST

Name of Work :-		Panchgachhi Road to L029 Kharra Belbari 1st
Block :-		Terhagachh
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 9,14,549 = 00
B	Add 12 % GST	Rs 1,09,746 = 00
C	Add 1 % L. Cess	Rs 9145 = 00
D	Add S.Fee @ 10 % of Material Cost	Rs 28,217
	Total Cost with GST, LC & S.Fee	Rs 10,61,657 = 00


13/9/21
J.E
RWD
Terhagachh


13.09.2021
A.E
R.W.D
Terhagachh


E.E
R.W.D
Kishanganj - I

Detailed Estimate

Detailed Estimate												
Name of Work :-			Panchgachhi Road to L029 Kharra Belbari 1st									
Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	WRD	5.7.7	Providing bamboo piles including labour for cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc complete job as per specification and direction of E/I	1	270	2.80	-	-	756.00			
				0	0	0.00	-	-	0.00			
			Total:-						756.00	Mtr.	55.40	41882.00
3	WRD	5.7.9	Supplying, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails, all material and labour complete job as per specification and direction of E/I.	3	75	3.00	-	-	675.00			
				0	0	0.00	-	-	0.00			
			Total:-						675.00	Mtr.	30.87	20837.00
6	9.2 (i)	1100 & 800	Sand filling or Type B (First class) bedding									
			Fillling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9									
				1	1	75.00	0.80	1.00	60.00			
				1	1	82.00	1.00	0.90	73.80			
				1	3	30.00	1.00	0.80	72.00			
				1	1	24.00	1.00	0.80	19.20			
			Total:-						225.00	Cum	514.43	115747.00
7	WRD	5.7.40	Brick bats									
			Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I									
				1	1	75.00	0.80	0.60	36.00			
				1	1	82.00	1.00	0.60	49.20			
				1	3	30.00	1.00	0.65	58.50			
				1	1	24.00	1.00	0.65	15.60			3,45,477=
			Total:-						85.20	Cum	2168.72	184775.00
13		5.7.53	Providing and filling empty cement bags						159.30			
			Supply of new bag with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stitching on two line by approved nylon thread with stitching machine & generator, stacking the bags and placing with a lead of 150m including supply of nylon threads etc all complete as per approved design, specification and direction of E/I.									
				1	1	75.00	0.80	1.90	114.00			
				1	1	82.00	0.80	1.50	98.40			
				1	3	30.00	1.20	1.00	108.00			
				1	1	24.00	1.20	1.00	28.80			
			Total:-						349.20	Cum		
			@ 0.034 Cum each bag						10271	No.	38.03	390606.00
			TOTAL									753847.00

3,45,477 = 00

9,14,543 = 00

Sami
13/01/24
J.E
RWD
Terhagachh

13.05.2024
A.E
R.W.D
Terhagachh

E.E
R.W.D
Kishanganj - I

ABSTRACT OF QUANTITY & COST

Item of Works	Quantity	Unit	Earth Work	Stone Materials			Brick Bats	Local Sand	Total
				26.5mm to 9.50mm	9.50mm to 4.75mm	4.75mm below			
Earth Work:-	0.00	Cum	0.000	-	-	-	-	-	
SSB (Gr.-II):-	0.00	Cum	-	0.000	0.000	0.000	-	-	
Brick Bats:-	159.30 85.20	Cum	-	-	-	-	102.240 191.16	-	
Local Sand Filling:-	225.00	Cum	-	-	-	-	-	225.000	
Providing & Filling Empty Cement Bags:-	10271.00	No.	-	-	-	-	-	349.214	
Providing & Filling Empty Cement Bags in Nylon Crate:-	0.00	No.	-	-	-	-	-	0.000	
							191.16		
Total Quantity:-			0.000	0.000	0.000	0.000	102.240	574.214	
Rate:-			Rs 34.78	Rs 285.35	Rs 285.35	Rs 285.35	Rs 1050.00	Rs 141.85	
Total Amount:-			0.00	0.00	0.00	0.00	2,007.18	81452.00	Rs 2,82,170.00
							S.Fee@10% of M.Cost:-		Rs 28,217.00

Sd/-
13/9/21
JE/RWD
Terhagachh

AE/RWD
Terhagachh

EE/RWD
Kishanganj-1

ABSTRACT OF COST

Name of Work :-		Panchgachhi Road to L029 Kharra Belbari 2nd
Block :-		Terhagachh
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 415911.00
B	Add 12 % GST	Rs 49909.00
C	Add 1 % L. Cess	Rs 4159.00
D	Add S.Fee @ 10 % of Material Cost	Rs 13336.00
	Total Cost with GST, LC & S.Fee	Rs 483315.00

Sanj
13/9/24
J.E
RWD
Terhagachh


13.09.2024
A.E
R.W.D
Terhagachh


E.E
R.W.D
Kishanganj - I

Detailed Estimate

Name of Work :-			Panchgachhi Road to L029 Kharra Belbari 2nd									
Sl. No.	SDB Sl. No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	WRD	5.7.7	Providing bamboo piles including labour for cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc complete job as per specification and direction of E/I	1	270	2.80	-	-	756.00			
				0	0	0.00	-	-	0.00			
				Total:-					756.00	Mtr.	55.40	41882.00
3	WRD	5.7.9	Supplying, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails, all material and labour complete job as per specification and direction of E/I.	3	75	3.00	-	-	675.00			
				0	0	0.00	-	-	0.00			
				Total:-					675.00	Mtr.	30.87	20837.00
6	9.2 (i)	1100 & 800	Sand filling or Type B (First class) bedding Filling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9	1	1	10.00	6.00	2.00	120.00			
				1	1	10.00	6.00	1.90	114.00			
				1	1	6.00	6.00	1.90	68.40			
				1	1	20.00	1.00	0.80	16.00			
				Total:-					318.40	Cum	514.43	163795.00
7	WRD	5.7.40	Brick bats Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I	1	1	10.00	3.00	0.80	24.00			
				1	1	10.00	3.80	0.60	22.80			
				1	1	6.00	3.90	0.60	14.04			
				1	1	20.00	1.00	0.30	6.00			
				Total:-					66.84	Cum	2168.72	144957.00
10			RCC Pipe NP3 as per design in Single Row (600mm Dia.) Providing and laying reinforced cement concrete pipe NP3 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry works in head walls and parapets Clause 1106.	1	3	2.50	-	-	7.50			
				0	0	0.00	-	-	0.00			
				Total:-					7.50	Mtr.	1747.13	13103.00
13		5.7.53	Providing and filling empty cement bags Supply of new bag with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stitching on two line by approved nylon thread with stitching machine & generator, stacking the bags and placing with a lead of 150m Including supply of nylon threads etc all complete as per approved design, specification and direction of E/I.	1	2	10.00	0.80	0.70	11.20			
				1	2	6.00	0.60	1.00	7.20			
				1	1	20.00	0.60	0.80	9.60			
				Total:-					28.00	Cum		
				@ 0.034 Cum each bag					824	No.	38.03	31337.00
											TOTAL	415911.00

Samp
13/9/24
J.E
RWD
Terhagachh

A.E
13.09.2024
R.W.D
Terhagachh

R.W.D
Kishanganj - I

ABSTRACT OF QUANTITY & COST

Item of Works	Quantity	Unit	Earth Work	Stone Materials			Brick Bats	Local Sand	Total
				26.5mm to 9.50mm	9.50mm to 4.75mm	4.75mm below			
Earth Work:-	0.00	Cum	0.000	-	-	-	-	-	
SB (Gr.-II):-	0.00	Cum	-	0.000	0.000	0.000	-	-	
Brick Bats:-	66.84	Cum	-	-	-	-	80.208	-	
Local Sand filling:-	318.40	Cum	-	-	-	-	-	318.400	
Providing & filling Empty Cement Bags:-	824.00	No.	-	-	-	-	-	28.016	
Providing & filling Empty Cement Bags in Nylon Rate:-	0.00	No.	-	-	-	-	-	0.000	
Total Quantity:-			0.000	0.000	0.000	0.000	80.208	346.416	
Rate:-			Rs 34.78	Rs 285.35	Rs 285.35	Rs 285.35	Rs 1050.00	Rs 141.85	
Total Amount:-			0.00	0.00	0.00	0.00	84218.00	49139.00	Rs 133357.00
							S.Fee@10% of M.Cost:-		Rs 13336.00

Sraj
13/9/24
JE/RWD
Terhagachh


13.09.2024
AE/RWD
Terhagachh


EE/RWD
Kishanganj-1