RURAL WORKS DEPARTMENT GOVT. OF BIHAR



Name of Work:- Ramkishore Mandal Home Behta to PMGSY Road Behta. Block:- Choraut.

F.D.R

Rs.321573.00 258847.10

Year-2021-22

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.



500

DETAILED ESTIMATE FOR F.D.R

Genearal Abstract of Cost

Name of Road:-Ramkishore Mandal Home Behta to PMGSY Road Behta.

Length of Road:-0.850 Km

Block:-Choraut

District - Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	2,70601.00
2	Labour cess @1%	2706.01
3	GST @12%	32472.12
4	Seigniorage Fee @ 10%	15794:11
5	Total Cost of Road Repair	321573:24

Say Rs.

321573.00

258847.00

AE

अभियन्ता-प्रमुख ग्रामीण कार्य विभाग के पत्रांक-4849 दिनांक-07 / 12 / 2021 के आदेशानुसार प्रशासनिक स्वीकृति के प्रत्याशा में औपवंधित तकनीकी स्वीकृति प्रदान की जा रही है। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त

पुनः तकनीकी स्वीकृति प्रदान की जायेगी। औपबंधित तकनीकी स्वीकृति रुपये. 2.58.8.47.00/-(Two laks Fifty geight housand eight hundred की प्रदान की जाती है।

रिक्रिंग Seven any

अधीक्षण अभियन्ता ग्रामीण कार्य विभाग

कार्य अंचल, सीतामढ़ी

Schedule of Quantity

ame of Road:-Ramkishore Mandal Home Behta to PMGSY Road Behta.

SI.		Qty	Unit	Rate	Amount
vo.	Description of Item	Qiy	Onte		
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	488.11	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machenical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	165.8000			0.00
	Less 20% for Voids	33.16		173225	229898
-	LICSS 20 /0 TOT YORK	132.6400	Cum	1823.81	241910.158 4
3	Single bamboo paiasiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	140.4	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stiching with sutall etc dodoall complete job as per specification and direction of E/I. (including Royalty and all Taxes)	0.00	no.	9,63	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	0.00	m	3400.00	0.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	0.00	m	850.00	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdoall complete job as per specification and diretion of E/I.			873.01	289 49.00
	Taking 20% of Brick Qty for Rabbish	33.16	Cum	_865.23	28691.026 27060T.


Total

270601.19

Say

270601.00

258847



Details of Measurement of ditches filled by brick bats and rabbish

Tame of Road:-Ramkishore Mandal Home Behta to PMGSY Road Behta.

	Nos.	L	W	H	VOLUME
CH 0.00 Km	1	30.00	3.000	0.300	27.0000
	1	30.00	3.000	0.300	27.0000
	1	30.00	3.000	0.300	27.0000
	1	30.00	3.000	0.250	22.5000
	1	30.00	3.000	0.300	27.0000
CH 0.210 Km	1	8.00	1.200	0.450	4.3200
	1	6.00	2.800	0.400	6.7200
	1	2.50	2.600	0.400	2.6000
	1	6.00	2.800	0.400	6.7200
	1	6.00	1.200	0.400	2.8800
	1	5.00	2.000	0.450	4.5000
	1	6.00	2.800	0.450	7.5600
		Total (in Cum)			165.8000
Laying Hume Pipe of 1000 mm dia		0	0	0	0.00
Laying Hume Pipe of 600 mm dia		0	0	0	0.00
Cement Bage		THE WAT			

JE JE

DKP ILTA-

AF

CEP HAVE STANDED

5.0

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

	मार्क साराज्ञ रहा । ।।। ।। वा सार	a forth and and article and
1	निरीक्षी पदाधिकारी का नाम एवं पदनाम:—	ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	20-12-2021
3	पथ का नाम (शीर्ष के साथ)	रामिकशोद संकटल होम बेहरा भी
4	पथ की लम्बाई	0.85 km
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	सुरसंड - नीरों त ।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	All Mesurment are attached in estimate Qty of Brick Bats:- 132.64m ³ Qty of Rubbish:- 33.11 m ³ Total Qty:- 135.8 m ³ Entered in MB No:- 2639 Page No:- 2
11	अस्थायी पुर्नस्थापन में किस–किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	<u>र्सनिय</u> द

निरीक्षी पदाधिकारी का हस्ताक्षर पदनाम सहित