



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. MOTRABLE RESTORATION (YEAR - 2021)

RCC BRIDGE AT POKHALI TO KE 2Nd KM TO VODRANI PATH AT CH. 7 KM

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 0	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	0.000	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.576	Lacs
ADD G.S.T @ 12%	Rs. 0.909	Lacs
ADD Labour Cess @ 1%	Rs. 0.076	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.367	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 8.928	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल किशनगंज -2 अन्तर्गत Thakurgaon.....
ब्रिज के पथ RCC Bridge at Pokhali to Ke. 2nd km to Verghani, Pothat Ch... जो
विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के
कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में Local Riv... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के
रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में
उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से
निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में
आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

अमर
13/10/21

उनीय अभियंता
ग्रामीण कार्य विभाग

कार्य प्रशाखा, Thakurgaon.....

सहायक
13/10/21

सहायक अभियंता
ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, Thakurgaon.....

अमर
13/10/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग

कार्य प्रमंडल किशनगंज-2

Inspection Report for Flood Damage Work

1. Name of PIUs

: Er. Uday Shanker Chudhary, E.E. Kishanganj-2

2. Name Of Block / Road

: Thakurganj / RCL Bridge at Powakhali to be 2nd km
to Vedra nipath at Ch-7 km.

A. For Road

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used In Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

:

N/A.

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

: 94M

3. Nature Of Damage

: Approach Road edge cutting.

4. Details Of Restoration

:

i) Material Being Used In Restoration

: Local Sand & Brick bats

ii) Equipment / Tools Being Used in Restoration Works

: Tractor.

iii) Procedure Taken Up In Restoration Works

: Manually

iv) Restored Length

: 24.0M

work has been completed. Satisfactory.

Signature of JE / AE / EE

Signature

(Name Of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : RCC BRIDGE AT POKHALI TO KE 2ND KM TO VODRANI PATH AT CH. 7 KM

DISTRICT KISHANGANJ

DIVISION KISHANGANJ - 2

BLOCK THAKURGANJ

LENGTH OF ROAD (IN KM) 0.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	LOCAL SAND	0.000
2	HUME PIPE	0.000
3	BRICK BATS	7.576
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.576
Add G.S.T. @ 12%		0.909
Add Labour Cess @ 1%		0.076
Add Seigniorage Fee @ 10%		0.367
Total Cost of Restoration Work =		8.928

Amya
15/10/21

J.E.
RWD

Arup
13/10/21

A.E.
RWD

Bh
16/12/21

E.E.
RWD

Technically Sanction for Rs 8,92,800.00 (Rupees Eight Lacs ninety two thousand Eight hundred) only.

Pallavi
04/04/22
E-0

Bh
04.04.22
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

RCC BRIDGE AT POKHALI TO KE 2ND KM TO VODRANI PATH AT CH. 7 KM

Sl. No.	SDB SL. NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
1	4.5		Brick Bats								
			Providing Brick Bats including, Spreading, Laying Compacting with C.I. Hammer all complete job as per Specification and Direction E/I.								
			C/O To ANNEXURE "B"						349.310		
				Cum					349.310	2168.720	757555.58
									Total Cost fo Flood Protective work (In Rs.) =		757555.58
									Total Cost fo Flood Protective work (In Lakh) =		7.576

Amey
13/10/21
JE.

Amey
13/10/21
A.E.

E.E.