



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

RANIKOL TO NARGADA (BRIDGE)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 64.62	
DISTRICT	KATIHAR	
BLOCK	KADWA	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	0.065	KM
TOTAL COST OF F.D.R. PART - A	Rs. 4.271	Lacs
ADD G.S.T @ 12%	Rs. 0.513	Lacs
ADD Labour Cess @ 1%	Rs. 0.043	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.219	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.046	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल ०१/१२/१३ अन्तर्गत ०२२५/१ प्रखंड के पथ (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

३९
३०/११/२१

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, ०२२५/१

३९
३०/११/२१

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, ०२२५/१

३९
३०/११/२१

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, ०१/१२/१३

Inspection Report for Flood damage work

Date:

1. Name of PIUs-

EE, RIND, Bassoi.

2. Name of Block/Road-

Kadwa, Ranikol to Nargada. (Bridge)

A. For Road

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works :

iii Procedure taken up in Restoration works :

iv Restored Length :

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works :

iii Procedure taken up in Restoration works :

iv Restored Length :

108.50 mt (Bridge Approach both side)

bamboo, piling, brick bats, etc.

Bamboo piling, Brick bats etc

GEB. with labour

108.50 mt

Signature of JE/AE/EE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : RANIKOL TO NARGADA (BRIDGE)

DISTRICT KATIHAR

DIVISION BARSOI

BLOCK KADWA

LENGTH OF ROAD (IN KM) 0.085

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BATS	4.025
4	SAND BAGS	0.000
5	BAMBOO WORK	0.246
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		4.271
Add G.S.T. @ 12%		0.513
Add Labour Cess @ 1%		0.043
Add Seigniorage Fee @ 10%		0.219
Total Cost of Restoration Work =		5.046

Ad
30/11/21
GEMH
30/11/21
J.E.
RWDAd
30/11/21
AS
RWDAd
30/11/21
E.E.
RWD

Provisional technically sanctioned for Rs 5.046 Lac (Rupees five lac four thousand six hundred) only.

अधीक्षक, आंचलिक
ग्रामीण कार्य विभाग
कार्य अंचल, पूर्णियाँ