



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

PWD LALBAGH CHOWK TO SIJ RATANPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1988	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	BARSOI MANIHARI	
TOTAL LENGTH OF ROAD	1.988	KM
TOTAL COST OF F.D.R. PART - A	Rs. 10.523	Lacs
ADD G.S.T @ 12%	Rs. 1.263	Lacs
ADD Labour Cess @ 1%	Rs. 0.105	Lacs
Add Seigniorage Fee @ 10 %	Rs. 0.571	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 12.462	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल सुनहरी अन्तर्गत सुनहरी..... प्रखंड के पथPWD Ladhagh Chowk to Sir Ratampur..... (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में प्रतिमान वर्ष 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 24-10-2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,सुनहरी.....


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,सुनहरी.....


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल,सुनहरी.....

33

Inspection Report for Flood damage work

Date:

1. Name of PIUs- RWD Manihari

2. Name of Block/Road- Manihari / PWD lalbagh Chowke to SJ Ratampur

A. For Road

1. Damage Location/Chainage : At different chainage.

2. Damage Length : 279m

3. Nature of Damage : shoulder.

4. Details of Restoration :

i Material being used in Restoration : Bricks Batts

ii Equipment/Tools being used in Restoration works: tractor

iii Procedure taken up in Restoration works :

iv Restored Length : 279m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :


4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :


Signature of JE/AE/EE


Signature


(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PWD LALBAGH CHOWK TO SIJ RATANPUR
DISTRICT KATIHAR
DIVISION BARSOI
BLOCK MANIHARI
LENGTH OF ROAD (IN KM) 1.988


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	BRIKCK BAT	10.484
2	SAND BAGS	0.000
3	BAMBOO WORK	0.039
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		10.523
Add G.S.T. @ 12%		1.263
Add Labour Cess @ 1%		0.105
Add Seigniorage Fee @ 10 %		0.571
Total Cost of Restoration Work =		12.462


JE
RWD


AE
RWD


EE
RWD

Technically Sanction for Rs.....12.462.....Lac (Rs.....
Crore.....Twelve.....Lac.....Twenty Six.....
Thousand.....Two.....Hundred.....)


Superintendent Engineer
Rural Works Department
Works Circle, Purnea