



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

PMGSY KUMARIPUR TO SIKARGANJ

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1115	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.115	KM
TOTAL COST OF F.D.R. PART - A	Rs. 4.333	Lacs
ADD G.S.T @ 12%	Rs. 0.520	Lacs
ADD Labour Cess @ 1%	Rs. 0.043	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.236	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.132	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन


पथ का नाम :- PMGSY Kumarippr To Sikarganj
पथ की लम्बाई :- 1.115 KM
प्राक्कलित राशि :- 5.132 Lac
वित्तीय वर्ष :- 2021-2022
प्रखंड :- Manihari

प्रस्तुत प्राक्कलन सी० 5.132 (पाँच लाख तेरह हजार दो सौ)

की राशि में ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत मनिहारी प्रखंड के S028 To Banfh Ganga पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाद एवं अतिवृष्टि के कारण क्षतिग्रस्त एवं पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक-मु० अ०-4 (मु०) विविध (कार्य)-23/291/2019-4275/पटना, दिनांक- 22.10.2021 के आलोक में यातायात(Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में क्षतिग्रस्त सड़क के फ्लैक/सरफेस को Bricks basts से भरकर आवागमन चाक किया गया है एवं सड़क पर होने वाली दुर्घटना को रोका गया है।


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पुर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है, प्राक्कलन की स्वीकृति जनहित में अति आवश्यक हैं।


25/11/21

कनीय अभियंता

ग्रामीण कार्य विभाग


कार्य प्रशाखा, मनिहारी


25/11/21

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, मनिहारी


25/11/21

कार्यप्रमुख अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs-

Manihari

2. Name of Block/Road-

PMGSY Kumariapur To Sikarganj

A. For Road

1. Damage Location/Chainage :

2. Damage Length :

262.70 m/r

3. Nature of Damage :

Side channel cutting due to Flood

4. Details of Restoration :

i Material being used in Restoration :

Brick Bats

ii Equipment/Tools being used in Restoration works:

Tractor

iii Procedure taken up in Restoration works :

Manual

iv Restored Length :

262.70 m/r

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :


4. Details of Restoration :


i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :


Signature of JE/AE/EE


25/11/24
Ar


25/11/24
JE


Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PMGSY KUMARIPUR TO SIKARGANJ

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK MANIHARI

LENGTH OF ROAD (IN KM)	1.115
------------------------	-------

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	4.333
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
	TOTAL COST OF PROJECT =	4.333
	Add G.S.T. @ 12%	0.520
	Add Labour Cess @ 1%	0.043
	Add Seigniorage Fee @ 10%	0.236
	Total Cost of Restoration Work =	5.132

Ugma
25/11/21

**J.E.
RWD**

Singh 25/11/24

**A.E.
RWD**

11

E.E.
RWD

Technically Sanction for Rs. 5.132 Lac (Rs. 5132000)
 Create five Lac thirteen Thousand two Hundred. —

Superintendent Engineer
Rural Works Department
Works Circle, Purnea