



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

PLAN HEAD- FDR YEAR 2021-22

DISTRICT :- WEST CHAMPARAN

BLOCK :- Yogapatti

Estimate for Repair of Road breaches
(Damaged by Flood) for Motorability in
Fatehpur Chowk(Bettiah-Nawalpur Path) To
Sanichari Chowk tak path

LENGTH OF ROAD (in Km)- 8.5 KM
DAMAGED LENGTH OF THE ROAD - 0.800 Km

ESTIMATED COST -	34.730	Lacs
------------------	--------	------


SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BETTIAH

घोषणा-पत्र

1. इस प्राक्कलन को असंवद्ध कार्यपालक अभियन्ता से जाँच करा ली गयी है।
2. अस्थायी पुनर्स्थापन के सामग्री का समायोजन स्थायी पुनर्स्थापन के प्राक्कलन में कर ली गयी है।



सहायक अभियन्ता / कनीय अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया।


25.11.21

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2

पत्रांक-.....347...../ बगहा-2, दिनांक.....25/11/2021

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बगहा-2

में,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, बेतिया।

:- कार्य प्रमंडल, बेतिया में वर्ष 2021 के बाढ़ में क्षतिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जाँच के संबंध में।

- भवदीय पत्रांक-1325/बेतिया, दिनांक-14.11.2021 एवम् अभियन्ता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-मु0अ0-4(मु0) विविध (कार्य)-23-291 /2019-4589, दिनांक-13.11.2021।


प्र,

उपर्युक्त विषयक एवम् प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल, बेतिया द्वारा कराये गये मोटरेबुल पथों की सूची में अंकित पथों का अधोहस्ताक्षरी द्वारा सहायक ता के साथ निरीक्षण किया गया। निरीक्षण के दौरान कार्य प्रमंडल, बेतिया द्वारा प्रतिवेदित थों पर कार्य कराया गया है एवम् यातायात चालु है।

सादर सूचनार्थ एवम् अग्रेत्तर कार्रवाई हेतु समर्पित।
निरीक्षण किये गये पथों की सूची।

सहायक अभियन्ता
0का0वि0, का0प्र0, बगहा-2

विश्वासभाजन,


25.11.2021

कार्यपालक अभियन्ता
ग्रा0का0वि0, का0प्र0, बगहा-2

autan	Purvi champaran jila antargat nutan prkhand ke basvriya champaran chetriy gramini bank se sansraiya hote hua tilangi tak sadak nirman	7.3	1.56
autan	Jhakara Bazar To Hospital Gamariya Ward No-16 Via Purbi Tola	1.725	3.491
apatti	L051 to Laherva Tola	1.35	5.74
apatti	L144-Chandul to Chandpur (TRACK144)	0.75	3.79
apatti	DUMARI - MANDATPUR	5.814	9.929
apatti	Malahi Tola Kohlayaa To L028	1	3.069
apatti	pachaim champaran jila antargat chamainiya chauk se prathmik vidhyalay dhanwatiya chauk se pachim disa ki aur gowarhiya dalit basti P.M.G.S.Y road dalit ke samne se mirhasan miya ke dodha se pipra jagiraha khalwa tola hote hue rajkiye prathmik vidhyalay harpurwa . sarnathi siwir ke bagal se harpurwa katti ke pas P.M.G.S.Y road ko par karke Ahirwaliya Gandak nahar chauk tak.	6.5	8.658
apatti	L056-Bhawanipur to Ramna (TRACK56)	3.8	5.837
apatti	L091-Paltu Sah Ke Bagicha To Lakra (TRACK91)	2.755	7.078
apatti	L023 Dumari to Bakhi	1.2	4.236
apatti	L065-Kablapur to Dhawelwa Madarsa (TRACK65)	4.078	15.685
apatti	L053 Rampurwa to Dhobi tola	1.115	4.982
apatti	L065 to Kablapur virta	0.585	4.834
apatti	L047-T01 toBintoli (TRACK47)	1.26	2.514
apatti	Fatepur chowk(Bettiah-Nawalpur Path) to Shanichari chowk tak path	8.5	34.73
apatti	Ahiravlia Chowk MNP Road to Ahir Tola Gola Ghat	1.45	7.209
apatti	Nawalpur Chawk Se Sirkaieya tak Path Nirman	9.5	38.95
apatti	L116-Gardardahiya to Hariharpur Tola (TRACK116)	2.25	4.234
apatti	Dhadhwa to Mushar toli FDR	3.54	7.567
apatti	Trivent Chowk To Matkota Ahir Tola	0.785	16.38
apatti	Matkota to Dhanush Toli	0.855	4.98
apatti	MASHAROLI CHOWK - PATKHAULI	3.1	13.45
apatti	L052 Baghi Middle School to Nawka Tola	1.025	8.84
apatti	BETTIAH NAWALPUR - KHARATIA NAWALPUR FDR	12.56	11.21
apatti	Bettiah Nawalpur to Gora	5.39	6.78
apatti	Panchayat Raj hathiya Me Chorahi Bariyarpur Me Gandak Nahar Ke Upar Pul Kotwa Mai Sthan to Paschim ki Aur Jane Wali Path in Yogapatti Block Under NABARD	0.91	0.51
apatti	L027 Nawgawa to Madarpur (Track27)2700m In Yogapati Block office to Mardarpur	33.48	18.915
Total		386.183	914.474

Signature
25.11.21

Excutive Engineer
RWD (W). Div.-Bagaha-2

GENERAL ABSTRACT OF COST

ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR
MOTORABILITY IN FATEHPUR CHOWK(BETTIAH-NAWALPUR PATH) TO
SANICHARI CHOWK TAK PATH

DISTRICT - WEST CHAMPARAN

DIVISION - Bettiah

BLOCK - Yogapatti

LENGTH OF ROAD (in Km)- 8.5 KM

DAMAGED LENGTH OF THE ROAD - 0.800 Km

SL. No.	Item of Work	Amount
1	SAND FILLING	0.000 Lacs
2	BRICK BATS	30.280 Lacs
3	SAND BAGS	0.000 Lacs
4	BAMBOOS PILING AND RUNNER	0.000 Lacs
5	HUME PIPE	0.000 Lacs
	COST OF RESTORATION	30.280 Lacs
	ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST	0.514 Lacs
	ADD LABOUR CESS @ 1%	0.303 Lacs
	ADD GST @ 12%	3.634 Lacs
	TOTAL COST OF RESTORATION OF ROAD	34.730 Lacs

John
05-11-21

Junior Engineer

[Signature]

[Signature]

Asstt. Engineer

[Signature]
05-11-21

Executive Engineer

Technically Approved *Sanctioned* for Rs 3473000.00 (Thirty Four lac
seventy three thousand) only/-

[Signature]
25/11/21
Superintendent Engineer
Rural Works Department
Works Circle, Bettiah
Govt. of Bihar

Work:-

Estimate for Repair of Road breaches (Damaged by Flood) for Motorability In Fatehpur Chowk(Bettiah-Nawalpur Path) To Sanchari Chowk tak path

OR

Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
Material & Labour for sand filling Pitching in slope or on including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum		As Per Appendix I			0	443.80	0
Providing and Labour for laying dry graded Brick Bats Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running charge of roller driver and khalasi etc. all complete as per approved design, specification and direction of E/I.	cum		As Per Appendix II			1478.28	2048.30	3027960.92
Providing, Filling Sand Bag, Stitching and Placing etc. complete as per specification and direction of E/I.	Nos.					0	21.75	0.00
Providing and Labour for cutting 62 mm to 75 dia bamboo piles to size and making shoes and driving etc. complete job as per specification and direction of E/I.	RM					0.00	47.61	0.00
Providing and Labour for fitting & fixing 62 mm to 75 dia Bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails etc. complete job as per specification and direction of E/I.	RM					0.00	26.85	0.00
Providing and laying 1000 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM		0 Nos*2.5m			0.00	6167.44	0.00
Providing and laying 600 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM		0 Nos*2.5m			0.00	2577.90	0.00
TOTAL (in Re.)								3027960.92

Sanchari
05-11-2017
Junior Engineer,
Rural Works Department,
Works Section, Yogapatti

Sanchari
Assistant Engineer,
Rural Works Department,
Works Sub Division, Yogapatti

Sanchari
5-11-21
Executive Engineer,
Rural Works Department,
Works Division, Bettiah