

Inspection Report of Flood Damage work

Inspected By Benipuri,

Name of PIUs:- RWD Works Division, Darbhanga

Name of Block/Road:- 1027 PWD Tumukani to Kobi (UR 27)
(Baharu)

A. For Road

1. Damage Location Chainage:- 0 to 1 km
2. Damage Length :- 0.185 km
3. Nature of Damage :- Road surface damage
4. Details of Restoration Works

- i. Material being used in Restoration works:- Brick Bats
- ii. Equipment's /Tools being used in Restoration works:- JCB/Tractor, Labourers
- iii. Procedure taken up in Restoration works:- Laying of Brick Bat with Light Ramming
- iv. Restored Length:- 0.185 km


B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works

- i. Material being used in Restoration works:-
- ii. Equipment's /Tools being used in Restoration works:-
- iii. Procedure taken up in Restoration works:-
- iv. Restored Length:-

N/A

work found Satisfactory.



Signature of JE/AE/EE



Signature

(Name of Inspection)

FDR

DISTRICT :-	DARBHANGA	
BLOCK :-	BAHERI	
Name of Raad :-	L027 PWD Trimuhani to Kopi (VR27).	
	Length of the Road:-	1.882 KM.
	Effective Length	0.185 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work				Amount	
					(in Rs.)	
1	Cost for restoration				276688.50	3,53,374.20
2	Add 12 % GST				33202.62	42,404.90
3	Add 1 % Labour Cess				2766.88	3,533.74
4	Seigniorage Fee	Quantity (in cum)	Rate (in Rs.)	%		
	(Br. Bats) in cum 138	176.250	1032.00	10.00	14241.60	18,189.00
	Total cost:-				326899.6	4,17,501.85
	Say Rs.				326900.00	4,17,502.00

Say Rs. 326900.00 = 00

[Signature]
06.11.2021
Junior Engineer
Baheri

[Signature]
21/11/21
Assistant Engineer
Baheri

[Signature]
18/11/21
Executive Engineer
R.W.D.(W) Division, Darbhanga-1

दाईपलस मालमल, लीकल ड वीच मल डल ड मालमल ड
Technically sanctioned for Rs 326900.00 (Rs
Three lacs twenty six thousand nine hundred only)

[Signature]
18/11/21
Superintending Engineer
RWD, Works Circle, Darbhanga

[Signature]
15/12/22

Detailed estimate for making moterable road.

Name of Raad :- L027 PWD Trimuhanl to Kopl (VR27).

BLOCK :- BAHERI

DISTRICT :- DARBHANGA

R.W.D. Works Division Darbhanga-1

Sl. No.	Item	Unit	No.	L	B			D/H				Quantity	Rate	Amount
				Length (m)	Breadth (m)	Breadth (m)	Av. Breadth (m)	Depth / Height (m)	Depth / Height (m)	Depth / Height (m)	Av. Depth / Height (m)			
1	Labour and Placing Brick Bats with Light raming Including cost of brick bats by tractor													
				1st KM										
		cum	1	3.00			3.75	0.150	0.350		0.250	2.813		
		cum	1	30.00			3.75	0.350	0.450	0.25	0.400	45.000	27	
		cum	1	30.00			3.75	0.450	0.350	0.25	0.400	45.000	24.75	
		cum	1	12.00			3.75	0.350	0.150		0.250	11.250		
		cum	1	20.00			3.75	0.200	0.150		0.175	13.125		
		cum	1	30.00			3.75	0.150	0.200		0.175	19.688		
		cum	1	30.00			3.75	0.200	0.150		0.175	19.688		
		cum	1	30.00			3.75	0.150	0.200		0.175	19.688		
												176.250	2004.96	353374.20
												138.002		353374.20

276688.5

[Signature]
06.11.2021

Junior Engineer
Baheri

[Signature]
21/11/21

Assistant Engineer
Baheri

[Signature]
21/11/21

Executive Engineer
R.W.D.(W) Division, Darbhanga-1

Verified for SE Darbhanga L.N. - 2326 (B.M.) at 21/11/21 & corrected as per note.

[Signature]
21/11/21

[Signature]
21/11/21
H.E.

[Signature]
21/11/21