



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. MOTRABLE RESTORATION (YEAR - 2021)

L051-L050 TO DERAMARI (TRACK 51)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2100		
DISTRICT	KISHANGANJ		
BLOCK	THAKURGANJ		
DIVISION	KISHANGANJ - 2		
TOTAL LENGTH OF ROAD		2.100	KM
TOTAL COST OF F.D.R. PART - A		Rs. 10.505	Lacs
ADD G.S.T @ 12%		Rs. 1.261	Lacs
ADD Labour Cess @ 1%		Rs. 0.105	Lacs
ADD Seigniorage Fee @ 10%		Rs. 0.468	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 12.339	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल किशनगंज -2 अन्तर्गत Thakurgaon प्रखंड के पथ Losi-Losoi To Deomari (Track-51) (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में Local Rm अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।


प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


10/10/21

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, Thakurgaon


10/10/21

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, Thakurgaon


10/10/21

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल किशनगंज-2

Inspection Report for Flood Damage Work

1. Name of PIUs

: Er. Uday Sankar Choudhary, EE Kne-02

2. Name Of Block / Road

: Thakuraj / LD SI-LOSO to Desamori (Track-SI)

A. For Road

1. Damage Location / Chainage

: 980M

2. Damage Length

: 32M

3. Nature Of Damage

: Flank, Crust, Culverts

4. Details Of Restoration

: Brick bats, cement, Bag, Bamboo, Local

i) Material Being Used In Restoration

ii) Equipment / Tools Being Used In Restoration Works

: Tractor trolley, JCB

iii) Procedure Taken Up In Restoration Works

: Manually

iv) Restored Length

: 32M

B. For Bridge

1. Damage Location / Chainage

: 7

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

: 32M

Work has been completed & H' factors

Signature of JE / AE / EE

Signature

Signature

(Name Of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L051-L050 TO DERAMARI (TRACK 51)

DISTRICT KISHANGANJ

DIVISION KISHANGANJ - 2

BLOCK THAKURGANJ

LENGTH OF ROAD (IN KM) 2.100

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	LOCAL SAND	0.000
2	HUME PIPE	0.332
3	BRICK BATS	9.575
4	SAND BAGS	0.348
5	BAMBOO WORK	0.250
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		10.505
Add G.S.T. @ 12%		1.261
Add Labour Cess @ 1%		0.105
Add Seigniorage Fee @ 10%		0.468
Total Cost of Restoration Work =		12.339

[Signature]
J.E.
RWD

[Signature]
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs 1233900.00 (Rupees twelve lacs thirty three thousand nine hundred) only.

[Signature]
04/04/22
E.O.

[Signature]
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, किशानगंज

