



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

PMGSY AMDABADIH ROAD TO PARASBANI SANTHALI (KHJURIYA BISHANPUR)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 900	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.900	KM
TOTAL COST OF F.D.R. PART - A	Rs. 4.940	Lacs
ADD G.S.T @ 12%	Rs. 0.593	Lacs
ADD Labour Cess @ 1%	Rs. 0.049	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.269	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.851	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत मनिहारी प्रखण्ड के पथ PMAS, Ambudih, to Baraighani, Senthaki/Khagpur (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में विश्व १५ २०२० अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 12/11/2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

22/11/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, मनिहारी

25/11/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, मनिहारी

25/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs-

Manikari

2. Name of Block/Road-

PR954 Amdabadih Road To Parasbani Santhali
(Khusiya Bisampur)

A. For Road

1. Damage Location/Chainage :

2. Damage Length : 171.00 m/r

3. Nature of Damage :

4. Details of Restoration : Side Cauter cutting due to Flood.

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works: Bricks bats

iii Procedure taken up in Restoration works: Tractor

iv Restored Length : Manual
171.00 m/r

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature
25/11/24

Signature of JE/AE/EE

Signature
25/11/24
AE

Signature
25/11/24

Signature
25/11/24

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PMGSY AMDABADIH ROAD TO PARASBANI SANTHALI (KHJURIYA BISHANPUR)

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK MANIHARI

LENGTH OF ROAD (IN KM) 0.900

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	4.940
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		4.940
Add G.S.T. @ 12%		0.593
Add Labour Cess @ 1%		0.049
Add Seigniorage Fee @ 10%		0.269
Total Cost of Restoration Work =		5.851

Wdmm
25/11/21
J.E.
RWD

Sang
25/11/21
A.E.
RWD

l
E.E.
RWD

Technically Sanction for Rs. 5.851 Lac (Rs. 58,510)

Crossed Five Lac Eighty five

Thousand One Hundred.

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea