



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. MOTRABLE RESTORATION (YEAR - 2021)

SIYALDANGA CHOWK TO KHARKHARI SSB CAMP BORDER ROAD TAK

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2000	
DISTRICT	KISHANGANJ	
BLOCK	THAKURGANJ	
DIVISION	KISHANGANJ - 2	
TOTAL LENGTH OF ROAD	2.000	KM
TOTAL COST OF F.D.R. PART - A	Rs. 10.821	Lacs
ADD G.S.T @ 12%	Rs. 1.299	Lacs
ADD Labour Cess @ 1%	Rs. 0.108	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.524	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 12.752	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Kishanganj - 2

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल किशनगंज -2 अन्तर्गत दाकुवाँडा..... प्रखंड के पथ सिआकडाँगा चौक से खरखती एस.बी. रीम्य बोर्ड रोड तक..... (.....) जो विभागीय Online Moritring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में मौकल तट..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

अमर
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, दाकुवाँडा.....

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, दाकुवाँडा.....

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल किशनगंज-2

Inspection Report for Flood Damage Work

1. Name of PIUs

: Er. Uday Shankar Chaudhary, EE, Kishanganj-2

2. Name Of Block / Road

: Thakurganj / Siyaldanga Chowk to Kharakhat SS/B camp
Border Road take.

A. For Road

1. Damage Location / Chainage

: 1st 82km

2. Damage Length

: 350 M

3. Nature Of Damage

: Plank & Crust-

4. Details Of Restoration

:

i) Material Being Used In Restoration

: Brick bats.

ii) Equipment / Tools Being Used In Restoration Works

: Tractor & SCB

iii) Procedure Taken Up In Restoration Works

: Manually

iv) Restored Length

: 350 M

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

::

iv) Restored Length

:

N/A.

work has been completed satisfactory.

Signature
03/12/21

Signature
03/12/21

Signature of JE / AE / EE

Signature

Signature
03/12/21

(Name Of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : SIYALDANGA CHOWK TO KHARKHARI SSB CAMP BORDER ROAD TAK
DISTRICT KISHANGANJ
DIVISION KISHANGANJ - 2
BLOCK THAKURGANJ
LENGTH OF ROAD (IN KM) 2.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	LOCAL SAND	0.000
2	HUME PIPE	0.000
3	BRICK BATS	10.821
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		10.821
Add G.S.T. @ 12%		1.299
Add Labour Cess @ 1%		0.108
Add Seigniorage Fee @ 10%		0.524
Total Cost of Restoration Work =		12.752

Aymer
24/10/21
J.E.
RWD

Surf
24/10/21
A.E.
RWD

B. L.
16/12/21
E.E.
RWD

Technically sanction for Rs. 1275200=00 (Rupees twelve Lacs Seventy five thousand two hundred) only.

Pallavi
04/04/22
P.O.

B. L.
04/04/22
अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, किशानगंज

SIYALDANGA CHOWK TO KHARKHARI SSB CAMP BORDER ROAD TAK

Sl. No.	SDB SL. NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	4.5		Brick Bats Providing Brick Bats including, Spreading, Laying Compacting with C.I. Hammer all complete job as per Specification and Direction E/I.								
			C/O To ANNEXURE "B"						498.960		
				Cum					498.960	2168.720	1082104.53
									Total Cost fo Flood Protective work (In Rs.) =		1082104.53
									Total Cost fo Flood Protective work (In Lakh) =		10.821

Aymer
24/10/14
JE.

for
24/10/14

A.E.

E.E.