



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

PLAN HEAD- FDR YEAR 2021-22

DISTRICT :- WEST CHAMPARAN
BLOCK :- Yogapatti

Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in Chandraul To Chandpur

LENGTH OF ROAD (in Km)- 0.75 KM
DAMAGED LENGTH OF THE ROAD - 0.130 Km

ESTIMATED COST -	4.980	Lacs
------------------	-------	------


SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BETTIAH

घोषणा-पत्र

1. इस प्राक्कलन को असंबद्ध कार्यपालक अभियन्ता से जाँच करा ली गयी है।
2. अस्थायी पुनर्स्थापन के सामग्री का समायोजन स्थायी पुनर्स्थापन के प्राक्कलन में कर ली गयी है।



सहायक अभियन्ता / कनीय अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया।


25.11.21

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2

पत्रांक- 847 / बगहा-2, दिनांक 20/11/2021

क:-

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बगहा-2

वा में,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, बेतिया।

षय :-

कार्य प्रमंडल, बेतिया में वर्ष 2021 के बाढ़ में क्षतिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जांच के संबंध में।

ंग:-

भवदीय पत्रांक-1325/बेतिया, दिनांक-14.11.2021 एवम् अभियन्ता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-मु0अ0-4(मु0) विविध (कार्य)-23-291 / 2019-4589, दिनांक-13.11.2021।

शय,

उपर्युक्त विषयक एवम् प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल, बेतिया द्वारा संध कराये गये मोटरेबुल पथों की सूची में अंकित पथों का अधोहस्ताक्षरी द्वारा सहायक यन्ता के साथ निरीक्षण किया गया। निरीक्षण के दौरान कार्य प्रमंडल, बेतिया द्वारा प्रतिवेदित पथों पर कार्य कराया गया है एवम् यातायात चालु है।

सादर सूचनार्थ एवम् अग्रेत्तर कार्रवाई हेतु समर्पित।

- निरीक्षण किये गये पथों की सूची।

सहायक अभियन्ता

का0वि0, का0प्र0, बगहा-2

विश्वासभाजन,

[Signature]
25.11.2021

कार्यपालक अभियन्ता

ग्रा0का0वि0, का0प्र0, बगहा-2

atan	Purvi champaran jila antargat nutan prkhand ke basvriya champaran chettri gramian bank se sansraiya hote hua tilangi tak sadak nirman	7.3	1.56
atan	Jhakara Bazar To Hospital Gamariya Ward No-16 Via Purbi Tola	1.725	3.491
patti	L051 to Laherva Tola	1.35	5.74
patti	L144-Chandrul to Chandpur (TRACK144)	0.75	3.79
patti	DUMARI - MANDATPUR	5.814	9.929
patti	Malahi Tola Kohlayaa To L028	1	3.069
patti	pachaim champaran jila antargat chamainiya chaulk se prathmik vidhyalay dhanwatiya chaulk se pachim disa ki aur gowarhiya dalit basti P.M.G.S.Y road dalit ke samne se mirhasan miya ke dodha se pipra jagiraha khalwa tola hote hue rajkiye prathmik vidhyalay harpurwa , sarnathi siwir ke bagal se harpurwa katti ke pas P.M.G.S.Y road ko par karke Ahirwaliya Gandak nahar chaulk tak.	6.5	8.658
patti	L056-Bhawanipur to Ramna (TRACK56)	3.8	5.837
patti	L091-Paltu Sah Ke Bagicha To Lakra (TRACK91)	2.755	7.078
patti	L023 Dumari to Bakhi	1.2	4.236
patti	L065-Kablapur to Dhawelwa Madarsa (TRACK65)	4.078	15.685
patti	L053 Rampurwa to Dhobi tola	1.115	4.982
patti	L065 to Kablapur virta	0.585	4.834
patti	L047-T01 to Bintoli (TRACK47)	1.26	2.514
patti	Fatepur chowk(Bettiah-Nawalpur Path) to Shanichari chowk tak path	8.5	34.73
patti	Ahiravlia Chowk MNP Road to Ahir Tola Gola Ghat	1.45	7.209
patti	Nawalpur Chawh Se Sirkaieya tak Path Nirman	9.5	38.95
patti	L116-Gardardahiya to Hariharpur Tola (TRACK116)	2.25	4.234
patti	Dhadhwa to Mushar toli FDR	3.54	7.567
patti	Trivent Chowk To Matkota Ahir Tola	0.785	16.38
patti	Matkota to Dhanush Toli	0.855	4.98
patti	MASHAROLI CHOWK - PATKHAULI	3.1	13.45
patti	L052 Baghi Middle School to Nawka Tola	1.025	8.84
patti	BETTIAH NAWALPUR - KHARATIA NAWALPUR FDR	12.56	11.21
patti	Bettiah Nawalpur to Gora	5.39	6.78
patti	Panchayat Raj hathiya Me Chorahi Bariyarpur Me Gandak Nahar Ke Upar Pul Kotwa Mai Sthan to Paschim ki Aur Jane Wali Path in Yogapatti Block Under NABARD	0.91	0.51
patti	L027 Nawgawa to Madarpur (Track27)2700m in Yogapati Block office to Mardarpur	33.48	18.915
	Total	386.183	914.474

Signature
25.11.21

Excutive Enginner
RWD (W). Div.-Bagaha-2

GENERAL ABSTRACT OF COST

ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR MOTORIBILITY IN CHANDRAUL TO CHANDPUR

DISTRICT - WEST CHAMPARAN

BLOCK - Yogapatti

DIVISION - Bettiah

LENGTH OF ROAD (in Km)- 0.75 KM

DAMAGED LENGTH OF THE ROAD - 0.130 Km

Item of Work	Amount
SAND FILLING :	0.000 Lacs
BRICK BATS :	4.342 Lacs
SAND BAGS :	0.000 Lacs
BAMBOOS PILING AND RUNNER :	0.000 Lacs
HUME PIPE :	0.000 Lacs
COST OF RESTORATION :	4.342 Lacs
ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST :	0.074 Lacs
ADD LABOUR CESS @ 1% :	0.043 Lacs
ADD GST @ 12% :	0.521 Lacs
TOTAL COST OF RESTORATION OF ROAD :	4.980 Lacs

John
25-11-2024

Junior Engineer

STIM

Asstt. Engineer

Arch
5-11-21

Executive Engineer

Sanctioned
Approved for Rs 498000 = 00 (Four Lacs
Nety eight thousand) only / -

Om
25/11/24
Superintendent Engineer
Rural Works Department
Works Circle, Bettiah
Govt. of Bihar

Work:-

Estimate for Repair of Road breaches (Damaged by Flood) for Motorability in Chandraul To Chandpur

R

Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
struction of embankment with approved material ined from borrow pits with a lift upto 1.5 m, sporting to site, spreading, grading to required e and compacting to meet requirement of Tables .1 and 300.2 with a lead upto 1000 m as per hnical Specification Clause 301.5	cum	As Per Appendix I				0	134.33	0
viding and Labour for laying dry graded Brick Bats Road Roller in proper grade camber and super vation dry and wet rolling including cost of running rge of roller diver and khalasi etc. all complete as approved design, specification and direction of E/I.	cum	As Per Appendix II				211.96	2048.30	434157.67
viding, Filling Sand Bag, Stitching and Placing etc. complete as per specification and direction of E/I.	Nos.					0	21.75	0.00
viding and Labour for cutting 62 mm to 75 dia bamboo piles to size and making shoes and driving complete job as per specification and direction of .	RM					0.00	47.61	0.00
viding and Labour for fitting & fixing 62 mm to 75 Bamboo runners in position at every virtical pile th 150 mm long nails or 38 swg G.I. wire including st of G.I. wire or nails etc. complete job as per ecification and direction of E/I.	RM					0.00	26.85	0.00
viding and laying 1000 mm dia reinforced cement ncrete pipe NP3 for culvert on first class bedding of anular material in single row excluding excavation, tection works, backfilling, concrete and masonry.	RM	0 Nos*2.5m				0.00	6140.12	0.00
viding and laying 600 mm dia reinforced cement ncrete pipe NP3 for culvert on first class bedding of anular material in single row excluding excavation, tection works, backfilling, concrete and masonry.	RM	0 Nos*2.5m				0.00	2566.97	0.00
TOTAL (In Re.)								434157.67

Satish
05-11-21

Junior Engineer,
Roads Works Department,
Bettiah Section, Yogapatti

ST
05-11-21

Assistant Engineer,
Rural Works Department,
Works Sub Division, Yogapatti

Devi
5-11-21

Executive Engineer,
Rural Works Department,
Works Division, Bettiah