



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MMGSY GOGAJHILL ROAD TO SURAPUR

### DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

|                                       |            |      |
|---------------------------------------|------------|------|
| ROAD LENGTH                           | 0 TO 4250  |      |
| DISTRICT                              | KATIHAR    |      |
| BLOCK                                 | MANIHARI   |      |
| DIVISION                              | MANIHARI   |      |
| TOTAL LENGTH OF ROAD                  | 4.250      | KM   |
| TOTAL COST OF F.D.R. PART - A         | Rs. 15.885 | Lacs |
| ADD G.S.T @ 12%                       | Rs. 1.906  | Lacs |
| ADD Labour Cess @ 1%                  | Rs. 0.159  | Lacs |
| ADD Seigniorage Fee @ 10%             | Rs. 1.701  | Lacs |
| TOTAL COST OF RESTORATION WORK In Rs. | Rs. 19.651 | Lacs |

SUBMITTED BY  
The Executive Engineer,  
Works Division, Manihari

प्रतिवेदन

पथ का नाम :- MMGSY Gogajhill To Surapar  
पथ की लम्बाई :- 4.250 KM  
प्राक्कलित राशि :- 19.684  
वित्तीय वर्ष :- 2021-2022  
प्रखंड :- Manihari

प्रस्तुत प्राक्कलन मो. 19.684 (अनिशु वाय असठ हजार तो)

की राशि में ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत मनिहारी प्रखंड के S028 To Banfh Ganga पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त एवं पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक-मु० अ०-4 (मु०) विविध (कार्य)-23/291/2019-4275/पटना, दिनांक- 22.10.2021 के आलोक में यातायात(Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में क्षतिग्रस्त सड़क के फलैंक/सरफेस को Bricks basts से भरकर आवागमन चालू किया गया है एवं सड़क पर होने वाली दुर्घटना को रोका गया है।


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है, प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।

  
25/11/21

कनीय अभियंता

ग्रामीण कार्य विभाग


कार्य प्रशाखा, मनिहारी

  
25/11/21

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, मनिहारी



कार्यमकल अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs- Manihari

2. Name of Block/Road- MMASY Gogardill To Surapar

A. For Road

1. Damage Location/Chainage : 2850 M at dibrut chaurge  
2. Damage Length : 210 M  
3. Nature of Damage : Soil with GSB wash out.  
4. Details of Restoration : Restored with soil filling brick baults and GSB.  
i Material being used in Restoration :  
ii Equipment/Tools being used in Restoration works: Tractor  
iii Procedure taken up in Restoration works : Measured  
iv Restored Length : 210 M

B. For Bridge

1. Damage Location/Chainage :  
2. Damage Length :  
3. Nature of Damage :  
4. Details of Restoration :  
i Material being used in Restoration :  
ii Equipment/Tools being used in Restoration works :  
iii Procedure taken up in Restoration works :  
iv Restored Length :

25/11/21

Signature of JE/AE/EE

Sgt 25/11/21  
AE

Signature

(Name of Inspector)

# GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : MMGSY GOGAJHILL ROAD TO SURAPUR

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK MANIHARI

LENGTH OF ROAD (IN KM) 4 250

| Sl. No.                          | ITEM OF WORK | AMOUNT (LAKHS) |
|----------------------------------|--------------|----------------|
| 1                                | EARTH WORK   | 4.652          |
| 2                                | HUME PIPE    | 0.727          |
| 3                                | BRIKCK BAT   | 10.506         |
| 4                                | SAND BAGS    | 0.000          |
| 5                                | BAMBOO WORK  | 0.000          |
| 6                                | GSB          | 0.000          |
| TOTAL COST OF PROJECT =          |              | 15.885         |
| Add G.S.T. @ 12%                 |              | 1.906          |
| Add Labour Cess @ 1%             |              | 0.159          |
| Add Seigniorage Fee @ 10%        |              | 1.701          |
| Total Cost of Restoration Work = |              | 19.651         |

See  
25/11/21  
J.E.  
RWD

Sary 25/11/21  
A.E.  
RWD

E.E.  
RWD

Technically Sanction for Rs. 19.651 Lac (Rs. ....  
Crore. Nineteen Lac sixty five.  
Thousand. One Hundred. ....

Superintendent Engineer  
Rural Works Department  
Works Circle, Purnea