

बा

RURAL WORKS DEPARTMENT GOVT. OF BIHAR



Name of Work:- Siya Ray Yadav Tola Hardiya To Hardiya Sukla Tola.
Block:- Pupri.

F.D.R


Rs788035.00 523675.00


Year-2021-22

Name of Circle:- R.W.D. Works Circle, Sitamarhi.

Name of Division:- R.W.D. Works Division, Pupri.

बाढ़ क्षतिग्रस्त पथों का अन्तर प्रमंडलीय जाँच प्रतिवेदन हेतु प्रपत्र

1	निरीक्षी पदाधिकारी का नाम एवं पदनाम:-	ई0 विनोद कुमार साह, कार्यपालक अभियंता, ग्रामीण कार्य विभाग, कार्य प्रमंडल, सीतामढ़ी।
2	निरीक्षण की तिथि:-	22-12-2021
3	पथ का नाम (शीर्ष के साथ)	Siya Ray Jadar Tol Hardiya To Hardiya Sukla Tola,
4	पथ की लम्बाई	1.300 Km
5	कार्य प्रमंडल का नाम	ग्रामीण कार्य विभाग, कार्य प्रमंडल, पुपरी।
6	प्रखंड का नाम	पुपरी।
7	पथ की स्थिति	(Completed/Ongoing)
8	पथ अनुरक्षण अवधि में हैं	(Yes/No)
9	क्षतिग्रस्त भाग की लम्बाई	
10	क्षतिग्रस्त भाग में कराये गये कार्य का विवरणी (लम्बाई x ऊँचाई x गहराई)	All Mesurment are attached in estimate Qty of Brick Bats :- 268.3448 m³ Qty of Rubbish:- 67.0862 m³ Total Qty :- 335.4310 m³ Entered in MB No:- 2670 Page No:- 3
11	अस्थायी पुर्नस्थापन में किस-किस सामग्रीयों को उपयोग किया गया है। उसकी विवरणी	Brick Bats & Rubbish
12	अभ्युक्ति	


 निरीक्षी पदाधिकारी का हस्ताक्षर
 पदनाम सहित

DETAILED ESTIMATE FOR F.D.R

General Abstract of Cost

Name of Road:-Siya Ray Yadav Tola Hardiya To Hardiya Sukla Tola.

Length of Road:-1.300 Km

Block:-Pupri

District:-Sitamarhi

S. No.	Particulars	Total Cost (in Lakh)
1	Total Cost for Motorable Roads	669099.00
2	Labour cess @1%	6690.99
3	GST @12%	80291.88
4	Seigniorage Fee @ 10%	31953.16
5	Total Cost of Road Repair	788035.03

Say Rs.

788035.00
523 675.00


JE


AE


CE

अभियंता प्रमुख ग्रामीण कार्य विभाग के पत्रांक-4849 दिनांक-07/12/2021


के आदेशानुसार प्रशासनिक स्वीकृति के प्रत्याशा में औपबंधित तकनीकी

स्वीकृति प्रदान की जा रही है। प्रशासनिक स्वीकृति प्राप्त होने के उपरान्त

पुनः तकनीकी स्वीकृति प्रदान की जायेगी।

औपबंधित तकनीकी स्वीकृति रुपये 523 675.00/- Five lakh twenty three thousand Six hundred

seventy five only की प्रदान की जाती है।


22/4/22

अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, सीतामढ़ी

Schedule of Quantity

Name of Road:-Siya Ray Yadav Tola Hardiya To Hardiya Sukla Tola.

Sl. No.	Description of Item	Qty	Unit	Rate	Amount
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification.	0.00	Cum	488.11	0.00
2	Providing and laying of Brick Bat obtained from Chimney with machanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	335.4310			0.00
	Less 20% for Voids	67.0862			465108.00
		268.3448	Cum	2105.01	564868.1874
3	Single bamboo paiasiding/ walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and Struts 1.5m apart longitudinally and providing brush wood as per drawing and technical specification clause 1302.5	0.00	m	140.4	0.00
4	Providing, Laying and placing empty cement bag filled with local sand including stiching with sutall etc. do.....do.....all complete job as per specification and direction of E/L. (including Royalty and all Taxes)	0.00	no.	9.63	0.00
5	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 1000) as per design in Single Row with old available pipe	0.00	m	3400.00	0.00
6	Providing and Laying Reinforced Cement Concrete Pipe NP3 (dia 600) as per design in Single Row with old available pipe	0.00	m	850.00	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks batsdo.....all complete job as per specification and direction of E/L.			873.01	58567
	Taking 20% of Brick Qty for Rabbish	67.0862	Cum	1553.68	104230.4872

Total 669098.97
Say 669099.00
523675.00


JE


AE


E

Details of Measurement of ditches filled by brick bats and rabbish

me of Road:-Siya Ray Yadav Tola Hardiya To Hardiya Sukla Tola.

	Nos.	L	W		H		VOLUME
CH 200 M	1	10.00	3.500	Av	0.950	Av	33.2500
	2	2.00	3.000		0.400	Av	4.8000
	1	3.00	2.800		0.650		5.4600
	1	6.00	3.000		0.650		11.7000
	1	2.50	2.000		0.400		2.0000
CH 250 M (N)	1	15.00	2.500		0.400		15.0000
	1	18.00	3.000	Av	0.600	Av	32.4000
	1	12.00	2.750	Av	0.400		13.2000
	1	8.00	2.200	Av	0.450	Av	7.9200
	2	4.00	0.500	Av	0.200	Av	0.8000
Link Road Jaychandra Das House Choraut	1	3.00	2.900		2.250		19.5750
	1	2.50	3.000		0.400		3.0000
	1	3.40	3.200		0.200		2.1760
	1	2.00	2.300		0.200		0.9200
	1	10.00	1.750		0.200		3.5000
	1	6.00	2.750		0.500		8.2500
	1	13.00	2.900		0.400		15.0800
	1	13.00	4.000		0.800		41.6000
Link Road Rizwan Ansari to Purvi Tola Balha	1	35.00	1.450		1.600		81.2000
	1	28.00	4.000		0.300		33.6000
Link Road Pokhar Bhinda to Gangapatti	1	28.00	4.000		0.300		33.6000
		Total (in Cum)					335.4310
Laying Hume Pipe of 1000 mm dia		0	0		0		0.00
Laying Hume Pipe of 600 mm dia		0	0		0		0.00
Cement Bage							


JE


AE


2-11-21