



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

KEWATIA BASTAUL TO SONAILI PWD ROAD TO BAINA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 10000	
DISTRICT	KATIHAR	
BLOCK	AZAMNAGAR <i>Poanpur</i>	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	10.000	KM
TOTAL COST OF F.D.R. PART - A	Rs. 41.801	Lacs
ADD G.S.T @ 12%	Rs. 5.016	Lacs
ADD Labour Cess @ 1%	Rs. 0.418	Lacs
ADD Seigniorage Fee @ 10%	Rs. 2.276	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 49.511	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत प्राजपुर प्रखंड के पथ कैवटिया बलौल से खोनेली पथ से हो के बना (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक **Moterable** हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से **Real time Geotagged Photographs** को कार्य के दौरान अपलोड करते हुए (**Moterable**) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु **Moterable** कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 31/10/21 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि **Geotagged Photographs Real Time** के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

Don
20/11/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, प्राजपुर

Sany
20/11/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, प्राजपुर

Don
20/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for Flood damage work

Date:

1. Name of PIUs- EE, RWD Manihari

2. Name of Block/Road- Paanpur, Kewariya Bastaul Sonaili Pad Road to Baina.

A. For Road

1. Damage Location/Chainage : CH- 1200m

2. Damage Length : 354.5m

3. Nature of Damage : Washout & flank Damage

4. Details of Restoration : filling brick base

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: Brick base tractor & JCD

iii Procedure taken up in Restoration works

iv Restored Length : Manual 354.5m

B. For Bridge

1. Damage Location/Chainage : N/A

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

[Signature]
20/11/24

Say 20/11/24
AE

[Signature]

Signature

(Name of Inspector)

Scanned with CamScanner

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : KEWATIA BASTAUL ~~TO~~ SONAILI PWD ROAD TO BAINA

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AZAMNAGAR *fourpura*

LENGTH OF ROAD (IN KM) 10.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	41.801
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		41.801
Add G.S.T. @ 12%		5.016
Add Labour Cess @ 1%		0.418
Add Seigniorage Fee @ 10%		2.276
Total Cost of Restoration Work =		49.511

On 26/11/24
J.E.
RWD

Sd/- 20/11/24
A.E.
RWD

[Signature]
E.E.
RWD

*Technically sanctioned for Rs 49.511 lacs (Rupees.
Forty nine lacs fifty one thousand & one
hundred / only .*

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea