



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

BAGHMARA TO MANIHARI

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 3000		
DISTRICT	KATIHAR		
BLOCK	MANIHARI		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD		3.000	KM
TOTAL COST OF F.D.R. PART - A		Rs. 4.591	Lacs
ADD G.S.T @ 12%		Rs. 0.551	Lacs
ADD Labour Cess @ 1%		Rs. 0.046	Lacs
ADD Seigniorage Fee @ 10%		Rs. 0.250	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 5.438	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत मनिहारी..... प्रखंड पथBaghmara To Manihari..... (.....) जो राष्ट्रीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक- /10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान लोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में सन्तमान वर्ष 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के डबे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांक 01-11-2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से कलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में वश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का इल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की जांच/प्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।



नीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, मनिहारी.....



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, मनिहारी.....



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी.....

Inspection Report for Flood damage work

Date:

1. Name of PIUs- RWD Marikani

2. Name of Block/Road- Marikani | Bughmara to Marikani

A. For Road

1. Damage Location/Chainage : At diff. Chainage

2. Damage Length : 142m

3. Nature of Damage : Surface of Road

4. Details of Restoration :

i Material being used in Restoration : Boide Bats

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works :

iv Restored Length : 142m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature
5/11/24
J-E

Signature of JE/AE/EE

Signature
5/11/24
AR

Signature

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BAGHMARA TO MANIHARI
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK MANIHARI
LENGTH OF ROAD (IN KM) 3.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	4.591
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		4.591
Add G.S.T. @ 12%		0.551
Add Labour Cess @ 1%		0.046
Add Seigniorage Fee @ 10%		0.250
Total Cost of Restoration Work =		5.438


25/11/21
J.E.
RWD


25/11/21
A.E.
RWD


25/11/21
E.E.
RWD

Technically Sanction for Re. 5.438 Lac (Rs. Five Forty three Thousand Eight Hundred Only)


Superintendent Engineer
Rural Works Department
Works Circle, Purnea