



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L053-T06 TO PHUGAON (VR53)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1100	
DISTRICT	KATIHAR	
BLOCK	BARSOI	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	1.100	KM
TOTAL COST OF F.D.R. PART - A	Rs. 11.124	Lacs
ADD G.S.T @ 12%	Rs. 1.335	Lacs
ADD Labour Cess @ 1%	Rs. 0.111	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.574	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 13.144	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi

Inspection Report for flood damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- L053-T06 TO PHUGAON (VR53) / BARSOI

A. For Road : L053-T06 TO PHUGAON (VR53).

1. Damage Location/Chainage : CH.

2. Damage Length : 63 M+8.

3. Nature of Damage : Shoulder and cry 8E

4. Details of Restoration : Bamboo Work and Brick Bat

i Material being used in Restoration

: Bamboo and Brick Bat

ii Equipment/Tools being used in Restoration works:

: JCB & Tractor

iii Procedure taken up in Restoration works

: Manually

iv Restored Length

: 63 M+8.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

12/5/21
AE

Signature

(Name of Inspector)


प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल बारसोई अन्तर्गत बारसोई प्रखंड के पथ L053-T06 TO PHUGAON LXR 53 (.....) जो विभागीय

Online Moritring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यात्रायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, बारसोई.....


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बारसोई

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L053-T08 TO PHUGAON (VR53)

DISTRICT KATIHAR

DIVISION BARSOI

BLOCK BARSOI

LENGTH OF ROAD (IN KM) 1.100

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	10.542
4	SAND BAGS	0.000
5	BAMBOO WORK	0.582
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		11.124
Add G.S.T. @ 12%		1.335
Add Labour Cess @ 1%		0.111
Add Seigniorage Fee @ 10%		0.574
Total Cost of Restoration Work =		13.144

(Signature)
JE
RWD
30.XI.0/21

(Signature)
A.E.
RWD
30.11.21

(Signature)
E.E.
RWD
30/11/21

Provisional Technically Sanctioned For Rs...13.144 Lacs.
(Rupees.....Crore...thirteen
acs...fourteen
Thousands...four...Hundred) Only

(Signature)
अधीक्षक ग्रामीण कार्य विभाग,
कार्य अंचल, पूर्णियाँ