



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L061-T02 TO GUNI TOLA (VR15) (DIVERSION)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 761		
DISTRICT	KATIHAR		
BLOCK	PRANPUR		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD	0.761	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 33.355	Lacs	
ADD G.S.T @ 12%	Rs. 4.003	Lacs	
ADD Labour Cess @ 1%	Rs. 0.334	Lacs	
ADD Seigniorage Fee @ 10%	Rs. 1.790	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 39.482	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत प्राणपुर प्रखंड के पथ 1061-T02 से मुन्नी टीला (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 25/11/21 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

25/11/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, प्राणपुर

20/11/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, प्राणपुर

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for Flood damage work

Date:

1. Name of PIUs- **EE RWD Manihari**

2. Name of Block/Road- **Panpur, Lohi - Tor to Guni tola (VRIS)**

A. For Road

1. Damage Location/Chainage : **CH- 450m.**
2. Damage Length : **141m**
3. Nature of Damage : **wash out**
4. Details of Restoration : **Brick batt filling.**
i Material being used in Restoration : **Brick batt**
ii Equipment/Tools being used in Restoration works : **tractor, job**
iii Procedure taken up in Restoration works :
iv Restored Length : **141m.**

B. For Bridge

1. Damage Location/Chainage : **N/A**
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works :
iii Procedure taken up in Restoration works :
iv Restored Length :

Signature of JE/AE/EE

[Signature]
20/11/24
17

[Signature]
Sany 20/11/24
172

[Signature]
20/11/24

Signature

(Name of Inspector)

Scanned with CamScanner

Scanned with CamScanner

Scanned with CamScanner

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L061-T02 TO GUNI TOLA (VR15) (DIVERSION)

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK PRANPUR

LENGTH OF ROAD (IN KM) 0.761

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.485
3	BRIKCK BAT	32.870
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		33.355
Add G.S.T. @ 12%		4.003
Add Labour Cess @ 1%		0.334
Add Seigniorage Fee @ 10%		1.790
Total Cost of Restoration Work =		39.482

[Signature]
J.E.
RWD

[Signature]
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanctioned for Rs 39.482 lacs (Rupees Thirty nine lacs forty eight thousand & two hundred) only.

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea