



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L059-T02 TO BALUA SANTHALI

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1067	
DISTRICT	KATIHAR	
BLOCK	PRANPUR	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.067	KM
TOTAL COST OF F.D.R. PART - A	Rs. 25.276	Lacs
ADD G.S.T @ 12%	Rs. 3.033	Lacs
ADD Labour Cess @ 1%	Rs. 0.253	Lacs
ADD Seigniorage Fee @ 10%	Rs. 1.376	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 29.938	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत प्राणपुर प्रखंड के पथ 1059-702 से अनुआ सेनाली (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 07/09/21 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, प्राणपुर

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, प्राणपुर

कार्यप्राप्त के अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs-

Mamihem

2. Name of Block/Road-

Poampor

A. For Road

L059 - T02 To Balua Santhauli

1. Damage Location/Chainage : CH-600m.

2. Damage Length : 133m.

3. Nature of Damage : wash out

4. Details of Restoration : filling Bricks bags

i Material being used in Restoration

: Bricks bags

ii Equipment/Tools being used in Restoration works:

: Tractor

iii Procedure taken up in Restoration works

: Manual

iv Restored Length

: 133m.

B. For Bridge

1. Damage Location/Chainage :

N/A

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration


ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE







Signature



(Name of Inspector)

Scanned with CamScanner

Scanned with CamScanner

Scanned with CamScanner

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L059-T02 TO BALUA SANTHALI


DISTRICT KATIHAR


DIVISION MANIHARI

BLOCK PRANPUR

LENGTH OF ROAD (IN KM) 1.067


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	25.276
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		25.276
Add G.S.T. @ 12%		3.033
Add Labour Cess @ 1%		0.253
Add Seigniorage Fee @ 10%		1.376
Total Cost of Restoration Work =		29.938


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically Sanction for Rs 29.938 lacs (Rupees twenty nine lacs ninety three thousand eight hundred) only


Superintendent Engineer
Rural Works Department
Works Circle, Purnea