



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L032-T02 TO AMDAUL (TRACK 12)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2250		
DISTRICT	KATIHAR		
BLOCK	PRANPUR		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD	2.250	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 33.627	Lacs	
ADD G.S.T @ 12%	Rs. 4.035	Lacs	
ADD Labour Cess @ 1%	Rs. 0.336	Lacs	
ADD Seigniorage Fee @ 10%	Rs. 1.831	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 39.829	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत प्राणपुर प्रखंड के पथ L082, T02 से अमजोल (TRACK 12) (.....) जो विभागीय Online Moritring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक **Moterable** हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु **Moterable** कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 19/11/21..... का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, प्राणपुर.....

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, प्राणपुर.....

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs: — EE RWD, Manihari

2. Name of Block/Road: Prampur, 1032 — 102 to Andaul (Trunk 12)

A. For Road

1. Damage Location/Chainage: CH — 1.800 Km.

2. Damage Length: 206m

3. Nature of Damage: flood wash out

4. Details of Restoration: Brick bazz filling

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: Brick bazz

iii Procedure taken up in Restoration works: Tractor & JCB

iv Restored Length

206m.

B. For Bridge

1. Damage Location/Chainage: N/A

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

Scanned with CamScanner

Scanned with CamScanner

Scanned with CamScanner

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L032-T02 TO AMDAUL (TRACK 12)

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK PRANPUR

LENGTH OF ROAD (IN KM) 2.250

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	33.627
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		33.627
Add G.S.T. @ 12%		4.035
Add Labour Cess @ 1%		0.336
Add Seigniorage Fee @ 10%		1.831
Total Cost of Restoration Work =		39.829

Comd
30/11/24
J.E.
RWD

Sany
20/11/24
A.E.
RWD

[Signature]
20/11/24
J.E.
RWD

Technically sanctioned for Rs 39.829 lacs. (Rupees thirty nine eighty two thousand & nine hundred only)

[Signature]
14/11/24
Superintendent Engineer
Rural Works Department
Works Circle, Purnea