



# ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

## DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L038 TO POKHAR TOLA

### DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1150	
DISTRICT	KATIHAR	
BLOCK	PRANPUR	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.150	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.406	Lacs
ADD G.S.T @ 12%	Rs. 0.889	Lacs
ADD Labour Cess @ 1%	Rs. 0.074	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.403	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 8.772	Lacs

SUBMITTED BY  
The Executive Engineer,  
Works Division, Manihari

## प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मानिहारी अन्तर्गत प्राणपुर प्रखंड के पथ 103.8 से पोखर टोला (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक **Moterable** हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से **Real time Geotagged Photographs** को कार्य के दौरान अपलोड करते हुए (**Moterable**) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में .....2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु **Moterable** कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 29/11/21 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि **Geotagged Photographs Real Time** के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

02/12/21  
20/11/21  
कनीय अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रशाखा, प्राणपुर

Sany 20/11/21  
सहायक अभियंता  
ग्रामीण कार्य विभाग  
कार्य अवर प्रमंडल, प्राणपुर

02/12/21  
कार्यपालक अभियंता  
ग्रामीण कार्य विभाग  
कार्य प्रमंडल, मानिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs- EE RD, Momin

2. Name of Block/Road- Panpur

A. For Road L038 To Pektur Talu

1. Damage Location/Chainage : CH- 200, 300, 350 etc.

2. Damage Length : 129.6m.

3. Nature of Damage : Road Cracks & flank Damage

4. Details of Restoration : Filling brick bats

i Material being used in Restoration : Bricks bats

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works : manual

iv Restored Length : 129.6m.

B. For Bridge

1. Damage Location/Chainage : N/A

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration : Bricks bats

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works : Manual

iv Restored Length :

Signature of JE/AE/EE

Com  
20/11/24

Sany  
20/11/24  
AE

20/11

Signature

(Name of Inspector)

**GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD**

NAME OF ROAD                      L038 TO POKHAR TOLA  
  
DISTRICT                              KATIHAR  
  
DIVISION                            MANIHARI  
BLOCK                               PRANPUR  
LENGTH OF ROAD (IN KM)      1.150

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	7.406
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.406
Add G.S.T. @ 12%		0.889
Add Labour Cess @ 1%		0.074
Add Seigniorage Fee @ 10%		0.403
Total Cost of Restoration Work =		8.772

*One*  
20/11/24  
J.E.  
RWD

*Savg*  
20/11/24  
A.E.  
RWD

*L*  
20/11/24  
E.S.  
RWD

*Technically Sanction for Rs 8.772 lacs. (Rupees eight lacs  
Seventy Seven thousand two hundred only)*

*[Signature]*  
20/11/24  
Superintendent Engineer  
Rural Works Department  
Works Circle, Purnea