



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L022 TO BHEMRA (DIVERSION)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 3100		
DISTRICT	KATIHAR		
BLOCK	PRANPUR		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD	3.100	KM	
TOTAL COST OF F.D.R. PART - A	Rs. 30.291	Lacs	
ADD G.S.T @ 12%	Rs. 3.635	Lacs	
ADD Labour Cess @ 1%	Rs. 0.303	Lacs	
ADD Seigniorage Fee @ 10%	Rs. 1.623	Lacs	
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 35.852	Lacs	

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल ममिहा अन्तर्गत प्राणपुर प्रखंड
के पथ 1022 से मीमरा (.....) जो
विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के
कारण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के
रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में
अपलोडेड फोटो दिनांक 28/11/21 का Lat/Long के साथ लिया गया है। नेपाल तराई से
निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में
आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, प्राणपुर

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, प्राणपुर

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, ममिहा

Inspection Report for Flood damage work

Date:

1. Name of PIUs- EE RWD Marikani

2. Name of Block/Road- Paampur

A. For Road L022 TO ~~BHENRA~~
BHENRA

1. Damage Location/Chainage : CH-200m.

2. Damage Length : 94m

3. Nature of Damage : washout

4. Details of Restoration : Brick bats filling

i Material being used in Restoration : Brick bats

ii Equipment/Tools being used in Restoration works: Tractor & JCB

iii Procedure taken up in Restoration works

iv Restored Length : 94m.

B. For Bridge

1. Damage Location/Chainage : N/A

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :


i Material being used in Restoration :


ii Equipment/Tools being used in Restoration works :

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE





Signature



(Name of Inspector)



up to 100%
checked
and
initialed


Scanned with CamScanner

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L022 TO BHEMRA (DIVERSION)
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK PRANPUR
LENGTH OF ROAD (IN KM) 3.100


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.485
3	BRIKCK BAT	29.806
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		30.291
Add G.S.T. @ 12%		3.635
Add Labour Cess @ 1%		0.303
Add Seigniorage Fee @ 10%		1.623
Total Cost of Restoration Work =		35.852


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically sanctioned for Rs. 36.852 lacs (Rupees.
thirty six lacs eighty five thousand & two hundred
only)


Superintendent Engineer
Rural Works Department
Works Circle, Purnea