



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

S069 PWD ROSHNA TO TELI TOLA WARD NO -1,2

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH

0 TO 1157

DISTRICT

KATIHAR

BLOCK

PRANPUR

DIVISION

MANIHARI

TOTAL LENGTH OF ROAD

1.157

KM

TOTAL COST OF F.D.R. PART - A

Rs. 11.167

Lacs

ADD G.S.T @ 12%

Rs. 1.340

Lacs

ADD Labour Cess @ 1%

Rs. 0.112

Lacs

ADD Seigniorage Fee @ 10%

Rs. 0.608

Lacs

TOTAL COST OF RESTORATION WORK In
Rs.

Rs. 13.227

Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत प्राणपुर प्रखंड के पथ S069 PWD सैशना रोड से तेजी रोला तराई न० (1,2...) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक **Moterable** हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से **Real time Geotagged Photographs** को कार्य के दौरान अपलोड करते हुए (**Moterable**) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु **Moterable** कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटेरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि **Geotagged Photographs Real Time** के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

Om
20/11/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, प्राणपुर

Sany
20/11/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, प्राणपुर

L
20/11/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for Flood damage work

Date:

EE RD

Name of PIUs-

Manikuni

Name of Block/Road-

Prembar

A. For Road

Sobq Prod Poshna Pathi To Teli Tola ward 1, 2

1. Damage Location/Chainage :

at Different 2 chainage

2. Damage Length :

259.5

3. Nature of Damage :

Road cross Damage & Flank Damage.

4. Details of Restoration :

filling Brick Jars

i Material being used in Restoration

Bricks bats,

ii Equipment/Tools being used in Restoration works:

Tractor

iii Procedure taken up in Restoration works

manually

iv Restored Length

259.5

B. For Bridge

1. Damage Location/Chainage :

N/A

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

JE

Sax 20/11/24
AE

20/11

Signature

(Name of Inspector)

Scanned with CamScanner

Scanned with CamScanner

Scanned with CamScanner

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : S069 PWD ROSHNA TO TELI TOLA WARD NO -1,2

DISTRICT KATIHAR


DIVISION MANIHARI

BLOCK PRANPUR

LENGTH OF ROAD (IN KM) 1.157


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	11.167
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		11.167
Add G.S.T. @ 12%		1.340
Add Labour Cess @ 1%		0.112
Add Seigniorage Fee @ 10%		0.608
Total Cost of Restoration Work =		13.227


J.E.
RWD


A.E.
RWD


B.E.
RWD

Technically Sanctioned for Rs. 13.227 lacs.
(^{Super}Thirteen lacs twenty two thousand &
seven hundred) only.


Superintendent Engineer
Rural Works Department
Works Circle, Purnea