



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MMGSY ROAD TO SREEJAN TOLA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 100	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.100	KM
TOTAL COST OF F.D.R. PART - A	Rs. 1.826	Lacs
ADD G.S.T @ 12%	Rs. 0.219	Lacs
ADD Labour Cess @ 1%	Rs. 0.018	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.063	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 2.126	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत मनिहारी प्रखंड के पथ MMGSY Road to Steegam tola (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-12/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में वर्तमान वर्ष 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के ओडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 13-08-2021 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।


प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।



ज्योती अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, मनिहारी।



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, मनिहारी।



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी।

3

Inspection Report for flood damage work (Year 2021-2022)

Date:

1. Name of PIUs- Rwa Manihari.

2. Name of Block/Road- Manihari / MMGSY Road to Sreejan Tola.

A. For Road

1. Damage Location/Chainage : 0 to 60m

2. Damage Length : 60m

3. Nature of Damage : Shoulder, soil washed underneath PCC.

4. Details of Restoration :

i Material being used in Restoration : Bricks Bat & Bamboo piling.

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works : Manual

iv Restored Length : 60m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :


4. Details of Restoration :


i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :


Signature of JE/AE/EE


Signature of JE/AE/EE




Signature
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : MMGSY ROAD TO SREEJAN TOLA

DISTRICT KATIHAR


DIVISION MANIHARI

BLOCK MANIHARI

LENGTH OF ROAD (IN KM) 0.100

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	1.161
4	SAND BAGS	0.000
5	BAMBOO WORK	0.665
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		1.826
Add G.S.T. @ 12%		0.219
Add Labour Cess @ 1%		0.018
Add Seigniorage Fee @ 10%		0.063
Total Cost of Restoration Work =		2.126


25/11/24
J.E.
RWD


25/11/24
A.E.
RWD


E.E.
RWD

Technically Sanction for Rs. 2.126 Lac (Rs. 2126 Crore. Two Lac Twelve Thousand Six Hundred. 00 Only)


Superintendent Engineer
Rural Works Department
Works Circle, Purnea