



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

PLAN HEAD- FDR YEAR 2021-22

DISTRICT :- WEST CHAMPARAN

BLOCK :- Yogapatti

Estimate for Repair of Road breaches
(Damaged by Flood) for Motorability in Triveni
Chowk To Matkota Ahir Tola

LENGTH OF ROAD (in Km)- 0.785 KM
DAMAGED LENGTH OF THE ROAD - 0.14 Km

ESTIMATED COST -	16.380	Lacs
------------------	--------	------


SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD WORKS DIVISION,
BETTIAH

घोषणा-पत्र

1. इस प्राक्कलन को अरांवद्ध कार्यपालक अभियन्ता से जाँच करा ली गयी है।
2. अस्थायी पुनरर्थापन के सामग्री का समायोजन स्थायी पुनरर्थापन के प्राक्कलन में कर ली गयी है।



सहायक अभियन्ता / कनीय अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया।


25.11.21

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, बेतिया

कार्यपालक अभियन्ता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमंडल, बगहा-2

पत्रांक-.....347...../ बगहा-2, दिनांक.....25/11/2021/

प्रेषक:-

कार्यपालक अभियन्ता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, बगहा-2

सेवा में,

अधीक्षण अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य अंचल, बेतिया।

विषय :-

कार्य प्रमंडल, बेतिया में वर्ष 2021 के बाढ़ में क्षतिग्रस्त पथों को मोटरेबुल कराने हेतु किये गये कार्यों की जाँच के संबंध में।

प्रसंग:-

भवदीय पत्रांक-1325/बेतिया, दिनांक-14.11.2021 एवम् अभियन्ता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना का पत्रांक-मु0अ0-4(मु0) विविध (कार्य)-23-291 /2019-4589, दिनांक-13.11.2021।

महाशय,

उपर्युक्त विषयक एवम् प्रासंगिक पत्र के अनुपालन में कार्य प्रमंडल, बेतिया द्वारा उपलब्ध कराये गये मोटरेबुल पथों की सूची में अंकित पथों का अधोहस्ताक्षरी द्वारा सहायक अभियन्ता के साथ निरीक्षण किया गया। निरीक्षण के दौरान कार्य प्रमंडल, बेतिया द्वारा प्रतिवेदित सभी पथों पर कार्य कराया गया है एवम् यातायात चालु है।

सादर सूचनार्थ एवम् अग्रेत्तर कार्रवाई हेतु समर्पित।

अनु0- निरीक्षण किये गये पथों की सूची।

विश्वासभाजन,


25.11.2021

सहायक अभियन्ता

ग्रा0का0वि0, का0प्र0, बगहा-2

कार्यपालक अभियन्ता

ग्रा0का0वि0, का0प्र0, बगहा-2

Nautan	Purvi champaran jila antargat nutan prkhand ke hasyriya champaran chetriy gramini bank se sansraiya hote hua tilangi tak sadak nirman	7.3	1.56
Nautan	Jhakara Bazar To Hospital Gamariya Ward No-16 Via Purbi Tola	1.725	3.491
Jogapatti	L051 to Laherva Tola	1.35	5.74
Jogapatti	L144-Chandrul to Chandpur (TRACK144)	0.75	3.79
Jogapatti	DUMARI - MANDATPUR	5.814	9.929
Jogapatti	Malahi Tola Kohlayaa To L028	1	3.069
Jogapatti	pachaim champaran jila antargat chamainiya chauk se prathmik vidhyalay dhanwatiya chauk se pachim disa ki aur gowarhiya dalit basti P.M.G.S.Y road dalit ke samne se mirhasan miya ke dodha se pipra jagiraha khalwa tola hote hue rajkiye prathmik vidhyalay harpurwa . sarnathi siwir ke bagal se harpurwa katti ke pas P.M.G.S.Y road ko par karke Ahirwaliya Gandak nahar chauk tak.	6.5	8.658
Jogapatti	L056-Bhawanipur to Ramna (TRACK56)	3.8	5.837
Jogapatti	L091-Paltu Sah Ke Bagicha To Lakra (TRACK91)	2.755	7.078
Jogapatti	L023 Dumari to Bakhi	1.2	4.236
Jogapatti	L065-Kablapur to Dhawelwa Madarsa (TRACK65)	4.078	15.685
Jogapatti	L053 Rampurwa to Dhobi tola	1.115	4.982
Jogapatti	L065 to Kablapur virta	0.585	4.834
Jogapatti	L047-T01 toBintoli (TRACK47)	1.26	2.514
Jogapatti	Fatepur chowk(Bettiah-Nawalpur Path) to Shanichari chowk tak path	8.5	34.73
Jogapatti	Ahiravlia Chowk MNP Road to Ahir Tola Gola Ghat	1.45	7.209
Jogapatti	Nawalpur Chawk Se Sirkaieya tak Path Nirman	9.5	38.95
Jogapatti	L116-Gardardahiya to Hariharpur Tola (TRACK116)	2.25	4.234
Jogapatti	Dhadhwa to Mushar toli FDR	3.54	7.567
Jogapatti	Trivent Chowk To Matkota Ahir Tola	0.785	16.38
Jogapatti	Matkota to Dhanush Toli	0.855	4.98
Jogapatti	MASHAROLI CHOWK - PATKHAULI	3.1	13.45
Jogapatti	L052 Baghi Middle School to Nawka Tola	1.025	8.84
Jogapatti	BETTIAH NAWALPUR - KHARATIA NAWALPUR FDR	12.56	11.21
Jogapatti	Bettiah Nawalpur to Gora	5.39	6.78
Jogapatti	Panchayat Raj hathiya Me Chorahi Bariyarpur Me Gandak Nahar Ke Upar Pul Kotwa Mai Sthan to Paschim ki Aur Jane Wali Path in Yogapatti Block Under NABARD	0.91	0.51
Jogapatti	L027 Nawgawa to Madarpur (Track27)2700m In Yogapatti Block office to Mardarpur	33.48	18.915
Total		386.183	914.474

[Signature]
25.11.21

Excutive Engineer
RWD (W). Div.-Bagaha-2

GENERAL ABSTRACT OF COST

ESTIMATE FOR REPAIR OF ROAD BREACHES (DAMAGED BY FLOOD) FOR
MOTORIBILITY IN TRIVENI CHOWK TO MATKOTA AHIR TOLA

DISTRICT - WEST CHAMPARAN

DIVISION - Bettiah

BLOCK - Yogapatti

LENGTH OF ROAD (in Km)- 0.785 KM

DAMAGED LENGTH OF THE ROAD - 0.14 Km

Item of Work	Amount
SAND FILLING	: 0.000 Lacs
BRICK BATS	: 13.341 Lacs
SAND BAGS	: 0.341 Lacs
BAMBOOS PILING AND RUNNER	: 0.131 Lacs
HUME PIPE	: 0.467 Lacs
COST OF RESTORATION	: 14.279 Lacs
ADD SEIGNIORAGE FEE @ 10% OF MATERIAL COST	: 0.245 Lacs
ADD LABOUR CESS @ 1%	: 0.143 Lacs
ADD GST @ 12%	: 1.713 Lacs
TOTAL COST OF RESTORATION OF ROAD	: 16.380 Lacs

Junior Engineer

Asstt. Engineer

Executive Engineer

Sanctioned
erically ~~Approved~~ for Rs 1638000 = 00 (Sixteen Lac
ixty eight thousand) only | -

Superintendent Engineer
Rural Works Department
Works Circle, Bettiah
Govt. of Bihar

Work:- Estimate for Repair of Road breaches (Damaged by Flood) for Motorability In Triveni Chowk To Matkota Ahir Tola

DR


Name of Item	unit	No	Length	Width	Height	Qty.	Rate	Amount
Material & Labour for sand filling Pitching in slope or on including light ramming etc. all complete as per approved design, specification and direction of E/I.	cum	As Per Appendix I				0	443.80	0
Providing and Labour for laying dry graded Brick Bats Road Roller in proper grade camber and super elevation dry and wet rolling including cost of running of roller driver and khalasi etc. all complete as approved design, specification and direction of E/I.	cum	As Per Appendix II				651.30	2048.30	1334057.79
Providing, Filling Sand Bag, Stitching and Placing etc. complete as per specification and direction of E/I.	Nos.					1566	21.75	34060.50
Providing and Labour for cutting 62 mm to 75 dia bamboo piles to size and making shoes and driving complete job as per specification and direction of	RM					148.00	47.61	7046.28
Providing and Labour for fitting & fixing 62 mm to 75 Bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails etc. complete job as per specification and direction of E/I.	RM					224.00	26.85	6014.40
Providing and laying 1000 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM	3 Nos*2.5m				7.50	6227.55	46706.63
Providing and laying 600 mm dia reinforced cement concrete pipe NP3 for culvert on first class bedding of granular material in single row excluding excavation, protection works, backfilling, concrete and masonry.	RM	0 Nos*2.5m				0.00	2601.94	0.00
TOTAL (in Re.)								1427885.60

W
-11-2021

Junior Engineer,
Works Department,
S Section, Yogapatti



Assistant Engineer,
Rural Works Department,
Works Sub Division, Yogapatti


5-11-21

Executive Engineer,
Rural Works Department,
Works Division, Bettiah