



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

YEAR-2020-21

DETAILED PROJECT REPORT

TEMPORARY RESTORATION WORK

DISTRICT :-

DARBHANGA

BLOCK :-

BAHADURPUR

ROAD NAME :

SH 50 TO KRISHINAPURI

HEAD

FDR

YEAR-2021-22

TOTAL LENGTH OF ROAD

:

0.715

KM

DAMAGE LENGTH

:

0.170

KM

TOTAL COST OF PROJECT

:

4.587

LAKH

Executive Engineer
RWD Darbhanga-1

4.607
4.297

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected by Benipur
Name of Block/Road:- SH 50 to Krishna/0421

A. For Road

1. Damage Location Chainage:- 500 M to 700 M
2. Damage Length :- 170 M
3. Nature of Damage :- Road crust damaged
4. Details of Restoration Works
 - i. Material being used in Restoration works:- Brice dal
 - ii. Equipment's /Tools being used in Restoration works:- S.C.B / tractor / labour
 - iii. Procedure taken up in Restoration works:- Laying of Brice dal with light Rammig
 - iv. Restored Length:- 170 M

B. For Bridge

1. Damage Location Chainage:-
 2. Damage Length :-
 3. Nature of Damage :-
 4. Details of Restoration Works
 - i. Material being used in Restoration works:-
 - ii. Equipment's /Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-
- N/A

were found satisfactory

Signature of JE/AE/EE



Signature

(Name of Inspection)

E.E. Benipur

प्रतिवेदन

पथ का नाम - SH 50 To KrishnaPuri
पथ की लंबाई - 0.215 KM
प्राक्कलित राशि - 4.797 लाख
प्रमंडल का नाम - Darbhanga-1
अंचल का नाम - Darbhanga
योजना का नाम -

SH 50 to KrishnaPuri

प्रस्तुत प्राक्कलन पथ के लिए तैयार किया गया है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।


यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0-4 (मु0) विविध (कार्य)-23-60/2020-1937 पटना, दिनांक-07.07.2021 के आलोक में तैयार किया गया है।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को मिट्टी एवं ईट के टुकड़ों से भरकर उसका संपीड़न किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचित दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।


कनीय अभियंता
ग्रामीण कार्य विभाग


सहायक अभियंता
ग्रामीण कार्य विभाग


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, दरभंगा-1

GENERAL ABSTRACT OF COST		
NAME OF ROAD :		SH 50 TO KRISHNAPURI
DISTRICT		DARBHANGA
BLOCK		BAHADURPUR
LENGTH OF ROAD (in Km)		0.715
DAMAGED LENGTH (KM)		0.17
Sl. No.	DESCRIPTION	AMOUNT
1	Cost of Restoration	405904.152
2	GST @12%	48708.498
3	Labour cess @1%	4059.042
4	Seigniorage	20872.08
5		-8.986
6	Grand Total	460761.458680.677
	Say(lacs)	4.607 -4.587

say 479665 = 00

JE
RWD

AE
RAWD

EE
RWD

कार्यपालक अभियंता बेनीपुर के जॉय प्रोविजन के आधार पर
Technically sanctioned for Rs 4,79,665 = 00 (Rupees
Four lacs seventy thousand six hundred sixty
five only)

अधिक्षण अभियंता
कार्य अंचल, दरभंगा
26/02/22

Detail Estimate For Motorable work of Road									
Name of road		Block			District		Division		Length(KM)
SH 50 TO KRISHNAPURI		BAHADURPUR			DARBHANGA		DARBHANGA-1		0.715
Sl. No.	Description	Unit	Nos	LENGTH	Avg. width	Avg Hight	Qty	RATE	AMOUNT (in Rs.)
1	Labour and Placing Brick bats with Light raming including cost of	0.50 cum	2.00	25	2.65	0.65	86.13		
			1.00	15	2	0.225	6.75		
			3.00	30	2.65	0.4	95.40		
			1.00	15	2.7	0.35	14.18		
DAMAGE LENGTH(M)					Total		202.45	2,004.96	4,05,904.15
0.17									

[Signature]
JE
RWD

[Signature]
AE
RWD

[Signature]
EE
RWD

Verified & found correct

[Signature]
15-12-21
JE

[Signature]
15/12/21
AE

[Signature]
15/12/21
EE Benipur