

ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

T02 TO BELGACHHI

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 730	
DISTRICT	KATIHAR	
BLOCK	PRANPUR	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.730	KM
TOTAL COST OF F.D.R. PART - A	Rs. 11.508	Lacs
ADD G.S.T @ 12%	Rs. 1.381	Lacs
ADD Labour Cess @ 1%	Rs. 0.115	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.613	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 13.617	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत प्राजापुर..... प्रखंड
पथ T02 से बेलागढ़ी..... (.....) जो

भागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 31.10.21..... का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बेट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, प्राजापुर.....

Sany 20/11/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, प्राजापुर.....

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for Flood Damage work

Date:

1. Name of PIUs- EE RWD MANIHARI

2. Name of Block/Road- Pampur

A. For Road Toz To Belgacchi

1. Damage Location/Chainage : CH- 32.5 m

2. Damage Length : 76m

3. Nature of Damage : wash out.

4. Details of Restoration : filling brick base

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works: Tractor & JCB

iii Procedure taken up in Restoration works

iv Restored Length : 76m

B. For Bridge

1. Damage Location/Chainage : N/A

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :


ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE




AE



Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T02 TO BELGACHHI

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK PRANPUR

LENGTH OF ROAD (IN KM) 0.730

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.242
3	BRIKCK BAT	11.266
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		11.508
Add G.S.T. @ 12%		1.381
Add Labour Cess @ 1%		0.115
Add Seigniorage Fee @ 10%		0.613
Total Cost of Restoration Work =		13.617

Om
20/11/21
J.E.
RWD

Sany
20/11/21
A.E.
RWD

K
20/11/21
E.E.
RWD

*Technically Sanction for Rs 13.617 lacs (Rupees thirteen
lacs sixty one thousand seven hundred) only.*

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea