

Sheosagar 1st copy

देमरी



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

T.S Copy

8.12.21

By SE

YEAR-2021-22

DETAILED PROJECT REPORT FOR MOTORABLE WORK

बिहार



DISTRICT :-	Rohtas	BLOCK :-	Sheosagar	
ROAD NAME :	Beda Dharsanadih Road to Semari			
HEAD	F.D.R.	YEAR-2021-22		
TOTAL LENGTH OF ROAD		:	2.420	KM
Damaged Length		:	0.015	M
TOTAL COST OF PROJECT		:	1.628	LAKH
Executive Engineer RWD Sasaram-1				

GENERAL ABTRACT OF COST

NAME OF ROAD: Beda Dharsanadih Road to Semari

DISTRIGT: Rohtas

BLOCK: Sheosagar

LENGTH OF ROAD (in Km) 2420.000

Damaged Length (M) 15

Sl. No.	DESCRIPTION	AMOUNT
1	Cost of Restoration	144081.677
2	GST @12%	17289.801
3	Labour cess @1%	1440.817
4	Seigniorage fee	0.000
5	Grand Total	162812.295
6	Say(lacs)	1.628

[Signature]
10.9.21

JE
RWD

[Signature]
10.09.21

AE
RWD

[Signature]
16/9/21

EE
RWD

[Signature]
7.12.21

[Signature]
7/12/21

[Signature]
19/11/21
EE RWD
Saxena 2

Technically approved for Rs 1.628 lacs
(one lacs sixty two thousand eight hundred only)

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, सासाराम

P.T.O.

Technically sanctioned for Rs 1,62,800 = 162,800/-
One lac Sixty two thousand eight hundred only.

અધીક્ષણ અધિયંત્ર
સમીપ કાર્ય વિભાગ
કર્મ અંગણ, સાચાર
ગાંધી

Detail Estimate For Motorable work of Road

Sl. No.	Name of road	Block			District	Division		Length (KM)
		Unit	Nos	LENGTH		Avg width	Avg Hight	
	Beda Dharsanadih Road to Semari				Rohtas			2.42
	Description							
1	Labour and Placing Brick bats with Light raming including cost of brick bats by tractor	cum	1.00	7.00	4.00 (avg)	2.60 (avg)	72.80	1,884.70
2	Suppling Fiting Fixing RCC H.P. Pipe 1000 mm dia	M	2.00	5.00	1.00 (avg)	1.00 (avg)	10.00	2,928.46
3	Deduction of H.M. Pipe Aea (2x2x2.5) Mtr	M	1.00	2.00	1.19	5.00	11.89	1,884.70
	Total							1,44,081.68

[Signature]
 07.12.21
 JE
 RWD

[Signature]
 10.09.21
 AE
 RWD

[Signature]
 21/12/21
 EE
 RWD

Inspection Report for Flood Damage Work

Date:- 15.09.21

Name of PIU- RWD WORK DIVISION, BASARAH-2

Name of Block/Road- Beda Darshandih Road to Serrau

(A) For Road-

1. Damage location/Chainage :- 15.00 m

2. Damage Length :- 7m

3. Nature of Damage :- Shoulder, BT SURFACE

4. Details of Restoration Works:-

(i) Material being used in Restoration Works:- BRICK BAT

(ii) Equipment's/Tools Being used in Restoration Works:- JCB, HYDRA

(iii) Procedure taken up in Restoration works:- BACKFILLING

(iv) Restored Length :- 7m

(B) For Bridge:

1. Damage location/Chainage :-

2. Damage Length :-

3. Nature of Damage :-


4. Details of Restoration Works:-

(i) Material being used in Restoration Works:-

(ii) Equipment's/Tools Being used in Restoration Works:-


(iii) Procedure taken up in Restoration works:-

(iv) Restored Length :-



15.09.21

Signature of JE

Signature of AE


15/9/21

Signature of EE


15/09/21

Signature

EE Serrau

(Name of Inspection)