



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

YEAR-2021-22

DETAILED PROJECT REPORT FOR MOTORABLE WORK

बिहार



DISTRICT :-

Rohtas

BLOCK :-

Chenari

ROAD NAME :

L079-T01 to Chitrataar (ODR44)

HEAD

F.D.R.

YEAR-2021-22

TOTAL LENGTH OF ROAD

: 1.650

KM

Damaged Length

: 75.000

M

TOTAL COST OF PROJECT

: 20.970

LAKH

Executive Engineer

RWD Sasaram-1

GENERAL ABTRACT OF COST

NAME OF ROAD : L079-T01 to Chitrataar (ODR44)

DISTRICT Rohtas

BLOCK Chenari

LENGTH OF ROAD (in Km) 1.650

Damaged Length (M) 75

Sl. No.	DESCRIPTION	AMOUNT
1	Cost of Restoration	1773526.259
2	GST @12%	212823.151
3	Labour cess @1%	17735.263
4	Seigniorage fee	92877.934
5	Grand Total	2096962.606
6	Say(lacs)	20.970

[Signature]
07.12.21

[Signature]
10.9.21
JE
RWD

[Signature]
10.09.21
AE
RWD
[Signature]
2.12.21

[Signature]
16/9/21
EE
RWD

[Signature]
19/11/21
EE RWD
Jaswan 2

(Technically Approved for Rs 20.97 lacs)
(Twenty lie only seven thousand only)

[Signature]
अधीकण अभियंता
ग्रामीण कार्य वि.
कार्य अंचल, सासाराम

Technically sanctioned for Rs 20,97,000 = 00
(Rupees Twenty lac ninety seven thousand) only

अधीक्षण अधिकारी
ग्रामीण कार्य विभाग
कार्य अंचल, सागरा-
डोईया

DETAILED ESTIMATE FOR PAVEMENT

FORM F6

Detail Estimate For Motorable work of Road

Detail Estimate For Motorable work of Road									
Name of road		Block		District		Division		Length(KM)	
L079-T01 to Chitrataar (ODR44)		Chenari		Rohatas		Sasaram-1		1.65	
Sl. No.	Description	Unit	Nos	LENGTH	Avg. width	Avg Hight	Qty	RATE	AMOUNT (in Rs.)
1	Labour and Placing Brick bats with Light raming including cost of brick bats by tractor	cum	1.00	5.00	2.45 (amt)	0.55 (amt)	6.74		
		cum	1.00	60.00	2.98 (amt)	5.15 (amt)	919.28		
		cum	1.00	10.00	2.50 (amt)	0.60 (amt)	15.00		
Total							941.01	1,884.70	17,73,526.26

7.12.21
JC

10.9.21
JE
RWD

10.09.21
AE
RWD
2.12.21

7/12/21
EE
RWD

Inspection Report for Flood Damage Work

Date:- 15-09-2021

Name of PIU- FWD WORKS DIVISION, SASARAM-1

Name of Block/Road- L079-701 to Chhitratar (OOR44)

(A) For Road:-

1. Damage location/Chainage :- 1150 m

2. Damage Length :- 75m

3. Nature of Damage :- Shoulder and BT

4. Details of Restoration Works:- Brick bat

(i) Material being used in Restoration Works:- ~~IEB~~ H. Brick bat

(ii) Equipment's/Tools Being used in Restoration Works:- JCB, Hydra

(iii) Procedure taken up in Restoration works:- Backfilling.

(iv) Restored Length :- 75m

(B) For Bridge:

1. Damage location/Chainage :-

2. Damage Length :-

3. Nature of Damage :-


4. Details of Restoration Works:-

(i) Material being used in Restoration Works:-


(ii) Equipment's/Tools Being used in Restoration Works:-


(iii) Procedure taken up in Restoration works:-

(iv) Restored Length :-


Signature of JE

Signature of AE


Signature of EE


Signature
EE Sasaram-2

(Name of Inspection)