

प्रखंड	पथ का नाम	कराए गए कार्य	मरम्मत कराए जाने हेतु पथ की लंबाई किलोमिटर	मरम्मत कराए जाने हेतु पथ की राशि	अंतिमवृत्ति
Shivajinagar	Kankar To Simrawan PMGSY Path to Bhorha Tola	Brick Bat Filling	0.3	5.43	पूर्ण
Shivajinagar	Dassut- Kakar Ghat	Brick Bat Filling	0.4	6.43	पूर्ण
Shivajinagar	Dhanka Chowk -Balipur Khander Chowk	Brick Bat Filling	0.415	3.21	पूर्ण
Shivajinagar	T01-Shankarpur	Brick Bat Filling	0.67	6.35	पूर्ण
Shivajinagar	L057-T01 To Mahadeva (VR32)	Brick Bat Filling	0.39	4.00	पूर्ण
Shivajinagar	Kariyan to Raniparti	Brick Bat Filling	0.395	3.60	पूर्ण
Shivajinagar	Rosera shivajinagar se Jakhar FDR	Brick Bat Filling	0.25	5.51	पूर्ण
Shivajinagar	L041 - T01 to Situahi (VR25)	Brick Bat Filling	0.295	5.60	पूर्ण
Shivajinagar	Karpuri Chouk To Manain Tole (Baghoupur)	Brick Bat Filling	0.315	2.84	पूर्ण
Shivajinagar	Maghrahia to Kharshan	Brick Bat Filling	0.35	3.43	पूर्ण
Shivajinagar	L049-T02 To Kankhariya (VR32)	Brick Bat Filling	0.25	2.60	पूर्ण
Shivajinagar	L040-T02 To Dharampur Punma (VR24)	Brick Bat Filling	0.4	3.64	पूर्ण
Shivajinagar	L067-L060 to Mahesar(VR49)	Brick Bat Filling	1.3	7.56	पूर्ण
Shivajinagar	Dhobiyahi se kharari siman tak path	Brick Bat Filling	0.29	2.65	पूर्ण
Shivajinagar	L022-T01 To Sahru (VR45)	Brick Bat Filling	0.3	3.31	पूर्ण
Shivajinagar	MDR Road to Moularahi Shirampur	Brick Bat Filling	0.18	1.97	पूर्ण
Shivajinagar	L046-T03 To Shahpur Navtolo (VR29)	Brick Bat Filling	0.475	3.76	पूर्ण
Shivajinagar	T01 - Dharampur Jakhar	Brick Bat Filling	0.7	2.14	पूर्ण
Shivajinagar	Borae Ranna to REO Road Rosera-Behari Road	Brick Bat Filling	0.35	3.48	पूर्ण
Shivajinagar	X-Road To L034 - Kolhatta	Brick Bat Filling	0.3	6.53	पूर्ण

Ram
21/2/21

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमंडल-गझौल-बरखडी

45



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR

FDR

YEAR 2021-22

Detailed Project Report

Division : Rosera

District :	Samastipur	Block :	ShivajiNagar
Name of Road :	<u>L057-T01To Mahadeva (VR32)</u>		

SUBMITTED BY
THE EXECUTIVE ENGINEER
WORKS DIVISION, ROSERA

तकनीकी प्रतिवेदन

पथ का नाम:- **L057-T01 T0 Mahadeva (VR32)**

प्राक्कलित राशि- 4.00 लाख


उपर्युक्त वर्णित पथ विगत बाढ़/बरसात वर्ष 2021-2022 से काफी छतिग्रस्त हो गए थे जिससे आवागमन काफी कठीनाईयुक्त हो गया था तथा दुर्घटनाए होती रहती थी जिसके कारण इस पथ को Brick bats आदि से भर कर मोटेरेबल किया गया है। पथ पर आवागमन जारी है।


Junior Engineer

RWD (w) Section, Bithan


Assistant Engineer

RWD (w) Sub Division, Bithan


Executive Engineer

RWD (w) Division, Rosera

FDR

Detailed Estimate for

L057-T0 To Mahadeva (VR32)

ShivajiNagar
Samastipur

ABSTRACT OF COST FOR ROAD

Item of Work		Amount (In Rs)	
		As per Estimate	
Total Cost for Pavement Works		Rs -	353996.74
Total Cost of Project :		Rs -	353996.74
Total Cost Including (GST + L.Cess) 13% :		Rs -	46019.58
Total :		Rs -	400016.31
Say (Lakh) :		Rs -	4.00

[Signature]
Junior Engineer

RWD (W) Section, ShivajiNagar

[Signature]
Asstt. Engineer

RWD (W) S. Div. Shivajinagar

[Signature]
Executive Engineer
RWD (W) Div, Rosera

Sanctioned
Approved for Rs 4.00 lac say four lakh only
with 13% GST charge.

[Signature]
10/11/21
T. A

[Signature]
10.12.21
10/11/21

45

FDR

L057-T0 To Mahadeva (VR32)

Total Length (Km): 0.39

Project : Samastipur		District : ShivajiNagar		Measurements			Unit	Quantity	Rate (Rs)	Amount (Rs)
Reference To Mord Spec.		Brief Description of Item		No	L (m)	B (m)	D (m)			
401	Supply filling brick bat compacted manually			7	30.00	2.00	0.30	cum	126.00	
				3	10.00	3.50	0.20	cum	21.00	
				4	5.00	2.60	0.40	cum	20.80	
				5	25.00	2.00	0.15	cum	37.50	
Total Quantity :								cum	205.30	1724.29
Total Cost of Pavement in Rs :										353996.74

Junior Engineer
RWD (W) Section, Shivajinagar

Asstt. Engineer
RWD (W) S. Div. ShivajiNagar

Executive Engineer
RWD (W) Div, Roseta