

Temporary Karkorath
Chenari - 2nd copy

कोट का केना



ग्रामीण कार्य विभाग

T.S Copy

Rural Works Department, Govt of Bihar

08.12.21

YEAR-2021-22

By SE

DETAILED PROJECT REPORT FOR MOTORABLE WORK

बिहार



DISTRICT :-	Rohtas	BLOCK :-	Chenari
ROAD NAME :	L113 Sheosagar - Raipurchore (Chenari Road) road to Chhotak Kenar VR93		
HEAD	F.D.R.	YEAR-2021-22	
TOTAL LENGTH OF ROAD		:	2805.000 KM
Damaged Length:		:	40.000 M
TOTAL COST OF PROJECT		:	1.099 LAKH

Executive Engineer
RWD Sasaram-1

GENERAL ABTRACT OF COST

NAME OF ROAD : L113 Sheosagar - Raipurchoe (Chenari Road) road to
Chhotak Kenar VR93
DISTRICT Rohtas
BLOCK Chenari
LENGTH OF ROAD (in Km) 2805.000
Damaged Length (M) 40

Sl. No.	DESCRIPTION	AMOUNT
1	Cost of Restoration	92746.087
2	GST @12%	11129.530
3	Labour cess @1%	927.461
4	Seigniorage fee	5055.112
5	Grand Total	109858.190
6	Say(lacs)	1.099

[Signature]
10.9.21
JE
RWD

[Signature]
10.09.21
AE
RWD
[Signature]
7.12.21

[Signature]
7/12/21
EE
RWD

[Signature]
19/11/21
EE (AWI)
Jasooam 2

(Technically approved for Rs 1.099 Lacs)
(one lac NINE thousand NINE hundred only)


[Signature]
17/11/21

अधीक्षणे अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, सासाराम

[Signature]
अधीक्षणे अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, सासाराम

P.T.O.

Technically sanctioned for Rs 1,09,900 = 10 (Ru)
One lac nine thousand nine hundred)


अधीक्षण अभियंता
प्रमाण कार्य विभाग
कार्य प्रचल, सामान्य
8/12/91

Detail Estimate For Motorable work of Road

Detail Estimate For Motorable Work on Road									
Name of road		Block		District	Division		Length(KM)		
L113 Sheosagar - Raipurchore (Chenari Road) road to Chhotak Kenar VR93		Chenari		Rohtas	Sasaram-I		2.805		
Sl. No.	Description	Unit	Nos	LENGTH	Avg. width	Avg Hight	Qty	RATE	AMOUNT (in Rs.)
1	Labour and Placing Brick bats with Light raming including cost of brick bats by tractor	cum	1.00	4.50	1.10 (over)	2.65 (over)	13.12		
2		M	1.00	4.00	1.40 (over)	2.35 (over)	13.16		
3		M	1.00	2.10	1.00 (over)	1.35 (over)	2.84		
4		M	1.00	1.45	0.90 (over)	1.45 (over)	1.89		
5		M	1.00	3.50	2.50 (over)	0.75 (over)	6.56		
6		M	1.00	13.20	0.90 (over)	0.65 (over)	7.72		
7		M	1.00	3.99	1.75 (over)	0.85 (over)	5.93		
Total							51.22	1,884.70	92,746.09

[Signature]
 10.9.21
 JE
 RWD

Abir
 10.09.21
 AE
 RWD

EE
 RWD
 7/10/21

Inspection Report for Flood Damage Work

Date:- 15.09.2021

Name of PIU- RWD WORKS DIVISION, SASARAM-3

Name of Block/Road- L 113 SheoSagar-Paipurchoke (Chenari Road)
Road to Chhotaka Kuar (VR 93)

(A) For Road-

- ~~Damage~~
1. Damage location/Chainage :- 1050 m
2. Damage Length :- 33 m
3. Nature of Damage :- Shoulder & BT

4. Details of Restoration Works:-


- (i) Material being used in Restoration Works:- Brick bat
(ii) Equipment's/Tools Being used in Restoration Works:- JCB, Hydra
(iii) Procedure taken up in Restoration works:- Backfilling
(iv) Restored Length :- 33 m

(B) For Bridge:


1. Damage location/Chainage :-
2. Damage Length :-
3. Nature of Damage :-


4. Details of Restoration Works:-

- (i) Material being used in Restoration Works:-
(ii) Equipment's/Tools Being used in Restoration Works:-
(iii) Procedure taken up in Restoration works:-
(iv) Restored Length :-


Signature of JE

Signature of AE


Signature of EE


Signature
EE Saran 2

(Name of Inspection)