

*Detail & estimation
found*



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

ESTIMATE FOR MOTORABILITY OF ROAD BREACHES DAMAGED BY FLOOD IN 2020

PLAN HEAD : 3054

YEAR : 2020-21

STATE :- BIHAR

DISTRICT :- MADHUBANI

BLOCK :- Kaluahi

Estimate for Motorability of Road NH 105 to Kazi Tol

DETAILED REPORT

TOTAL LENGTH OF ROAD

1.740 KM

TOTAL COST FOR MOTORABLE OF ROAD

1.33285 Lacs

1.483 Lacs.

SUBMITTED BY:
EXECUTIVE ENGINEER,
RWD, WORKS DIVISION,
MADHUBANI.

Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Kaluahi/NH-105 to Kazi tol

A. For Road

1. Damage Location Chainage:-

2. Damage Length :- 8m

3. Nature of Damage :- Damage of 1 km

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick Bat

ii. Equipments's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:- Brick Bat Filling

iv. Restored Length:-

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-


ii. Equipments's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

found satisfactory


Signature of JE/AE/EE


Signature
(Name of Inspector)

प्रतिवेदन

पथ का नाम : NH 105 to Kazi Tol
पथ का शीर्ष MMGSY
पथ की स्थिति : ONGOING
पथ का लंबाई 1.740 कि०मी०
क्षतिग्रस्त लंबाई 0.008 कि०मी०
प्राक्कलित राशि : ₹ ~~1.33~~^{1.483} लाख
प्रमंडल का नाम : मधुबनी
अंचल का नाम : दरभंगा
योजना शीर्ष : 3054
योजना वर्ष : 2020-21

प्रस्तुत प्राक्कलन NH 105 to Kazi Tol पथ में कराये गये यातायात पुनर्स्थापन कार्य के निमित्त तैयार की गयी है, जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/ जलजमाव/wave cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक मु०अ०-4 (मु०) विविध कार्य-23-116/17-2297(अनु०) पटना, दिनांक 12/07/2019 के आलाक में तथा दिनांक 20/10/2021 के विडियो कॉन्फ्रेंसिंग के माध्यम से दिये गये आदेश एवं अभियंता प्रमुख, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक मु०अ०-4 (मु०) विविध कार्य-23-291/2019-4275 पटना, दिनांक 22/10/2021 के द्वारा दिये गये समयबद्ध कार्यक्रम के आदेश के आलोक में तैयार किया गया है।

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश में बाढ़ के पानी के बहाव को बनाये रखने के लिए 1000 मिमी व्यास का ह्यूम पाईप को डालकर क्षतिग्रस्त पथ को आवागमन के लायक बनाने के लिए क्षतिग्रस्त भाग में ईट के टुकड़ों से भरकर उसको यातायात योग्य बनाये जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृत अनुसूचित दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस कराये गये कार्य के प्राक्कलन की Post Facto स्वीकृति अपेक्षित है।


कनीय अभियंता


29.10.21
सहायक अभियंता


30/10/21
कार्यपालक अभियंता

ead - MR 3054

Length : 1.74 KM

Say (in Re.) 133285.00

Junior Engineer,
Rural Works Department,
Works Section, Kaluahi -2

Assistant Engineer,
Rural Works Department,
Works Sub Division, Kaluahi

Executive Engineer,
Rural Works Department,
Works Division, Madhubani

Measurement checked & verified

Handwritten signatures and dates:

6/12/21
JE

6/12/21
JE

4/4
06/12/14
AZ

6/11/21

कृषिपालक अभियंता, शा.का.वि., कार्य प्रमंजल, बिरेल द्वारा क्षतिज औच प्रवेदन
के आधार पर
Post-facto Technically Sanctioned for Rs. 1,48,394.00 (Rs. one lakh forty eight
Thousand three hundred and ninety four only)

Superintending Engineer
P. W. D. (W) CIRCLE, DARBHANGA