


ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसाडा अंतर्गत FDR के तहत मरम्मत/Motorable कराए गये पथों की जाँच की सूची।

प्रखंड	पथ का नाम	कराए गए कार्य	मरम्मत कराए जाने हेतु पथ की लंबाई किलोमीटर	मरम्मत कराए जाने हेतु पथ की राशी	अभियुक्ती
shivajinagar	Kankar To Simrawan PMGSY Path to Bhorha Tola	Brick Bat Filling	0.3	5.43	पूर्ण
shivajinagar	Dassut- Kakar Ghat	Brick Bat Filling	0.4	6.43	पूर्ण
shivajinagar	Dhanka Chowk -Balipur Khander Chowk	Brick Bat Filling	0.415	3.21	पूर्ण
shivajinagar	T01-Shankarpur	Brick Bat Filling	0.67	6.35	पूर्ण
shivajinagar	L057-T01 To Mahadeva (VR32)	Brick Bat Filling	0.39	4.00	पूर्ण
shivajinagar	Kariyan to Raniparti	Brick Bat Filling	0.395	3.60	पूर्ण
shivajinagar	Rosera shivajinagar se Jakhar FDR	Brick Bat Filling	0.25	5.51	पूर्ण
shivajinagar	L041 - T01 to Situahi (VR25)	Brick Bat Filling	0.295	5.60	पूर्ण
shivajinagar	Karpuri Chouk To Manain Tole (Baghoupur)	Brick Bat Filling	0.315	2.84	पूर्ण
shivajinagar	Maghrahia to Kharshan	Brick Bat Filling	0.35	3.43	पूर्ण
shivajinagar	L049-T02 To Kankhariya (VR32)	Brick Bat Filling	0.25	2.60	पूर्ण
shivajinagar	L040-T02 To Dharampur Punma (VR24)	Brick Bat Filling	0.4	3.64	पूर्ण
shivajinagar	L067-L060 to Mahesar (VR49)	Brick Bat Filling	1.3	7.56	पूर्ण
shivajinagar	Dhobiyahi se kharari siman tak path	Brick Bat Filling	0.29	2.65	पूर्ण
shivajinagar	L022-T01 To Sahru (VR45)	Brick Bat Filling	0.3	3.31	पूर्ण
shivajinagar	MDR Road to Moularahi Shirampur	Brick Bat Filling	0.18	1.97	पूर्ण
shivajinagar	L046-T03 To Shahpur Navtolo (VR29)	Brick Bat Filling	0.475	3.76	पूर्ण
shivajinagar	T01 - Dharampur Jakhar	Brick Bat Filling	0.7	2.14	पूर्ण
shivajinagar	Borae Ranna to REO Road Rosera-Behari Road	Brick Bat Filling	0.35	3.48	पूर्ण
shivajinagar	X-Road To L034 - Kolhatta	Brick Bat Filling	0.3	6.53	पूर्ण

Ram
कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमंडल-गझौल-बरबडी



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR

FDR

YEAR 2021-22

Detailed Project Report

Division : Rosera

District :	Samastipur	Block :	Shivajinagar
------------	------------	---------	--------------

Name of
Road :

Majarahia To Kharsham

SUBMITTED BY
THE EXECUTIVE ENGINEER
WORKS DIVISION, ROSERA

FDR

Detailed Estimate for

Kharsham to Majrahia

Block : Sivajinagar
District : Samastipur

ABSTRACT OF COST FOR ROAD

No	Item of Work	Amount (In Rs)	
		As per Estimate	
	Total Cost for Pavement Works		303173.29
	Total Cost of Project :	Rs -	303173.29
	Total Cost Including (GST + L.Cess) 13% :	Rs -	39412.53
	Total :	Rs -	342585.82
	Say (Lakh) :	Rs -	3.43

Kamran
27/10/21

Junior Engineer

RWD (W) Section, Sivajinagar

U. Singh
27/10/21

Asstt. Engineer

RWD (W) S. Div. Sivajinagar

A. Singh
27/10/21

Executive Engineer

RWD (W) Div, Rosera

Sanctioned
Approved
3.43 Lakh say three Lakh forty
three thousand only including 0.17% chage.

Shyam
10/11/21
T.A.

Shyam
10.12.21
A.E.
10.12.21
बोर्डिंग बॉक्स
बोर्डिंग बॉक्स
बोर्डिंग बॉक्स

55

FDR
Kharsham to Majrabia

Project : Samastipur
Location : Sivajinagar

Total Length (Km): 0.350

Reference To Word Spec.	Brief Description of Item	No	Measurements			Unit	Quantity	Rate (Rs)	Amount (Rs)
			L (m)	B (m)	D (m)				
401	Supply filling brick bat compacted manually	1	40.00	2.00	0.250	cum	20.00		
		2	20.00	2.00	0.200	cum	16.00		
		2	8.00	2.00	0.300	cum	9.60		
		2	6.00	2.00	0.250	cum	6.00		
		3	4.00	2.00	0.300	cum	7.20		
		1	10.00	2.50	0.20	cum	5.00		
		1	10.00	2.50	0.15	cum	3.75		
		1	5.00	2.50	0.15	cum	1.88		
		1	5.00	2.30	0.10	cum	1.15		
		4	2.50	2.50	0.15	cum	3.75		
		4	30.00	3.50	0.150	cum	63.00		
		2	35.00	2.75	0.20	cum	38.50		
	Total Quantity :					cum	175.83	1724.29	303173.29
			Total Cost of Pavement in Rs :					3.03	

[Signature]
Junior Engineer
RWD (W) Section, Sivajinagar

[Signature]
Asstt. Engineer
RWD (W) S. Div. Sivajinagar

[Signature]
Executive Engineer
RWD (W) Div. Rosera