

SUMMARY OF COST ESTIMATE FOR THE PROJECT

NAME OF ROAD :- MMGSY To Jha Jee Tola
 DISTRICT :- Darbhanga
 BLOCK :- Singhwara
 Actual Length of Road :- 1.580 Km
 Flood Affected Length of Road :- 0.148 Km

		Lead in Km	3	+	1
Sr. No.	Description				Amount (In Rs.)
1	Brick bats Total Qty. = 116.72 ^{30.68} @ 1,874.91				2,18,831.00 ^{57,522.00}
2	Add GST @ 12%=				26,260.00 ^{6,903.00}
3	Add Labour Cess @ 1%=				2,188.00 ^{575.00}
4	S.F. @10% on material(Brick Bats)=				12,045.00 ^{3,166.00}
TOTAL RESTORATION COST OF THE PROJECT IN Rs.					2,59,324.00 ^{68,166.00}

- कार्यपालक अभियन्ता, ग्रामीण कार्य विभाग कार्य प्रमाणपत्र मधुबनी का पत्रांक - 595 अंकुश
 दिनांक - 12-03-2022 के द्वारा समर्पित जाँच प्रतिवेदन के आधार पर।
 - Post-facto T/A for Rs 68166.00 (Rs Sixty eight thousand one hundred sixty six only.)

Superintending Engineer,
 RWD (W) Circle Darbhanga

Junior Engineer
 RWD (W) Division, Darbhanga-2

Assistant Engineer
 RWD (W) Division, Darbhanga-2

Executive Engineer
 RWD (W) Division, Darbhanga-2

कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी।

पत्रांक:- 595 अनु०

दिनांक:- 12/03/2022

प्रेषक,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, मधुबनी।

सेवामें,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, दरभंगा-2

विषय:-

एफ0डी0आर0 योजनान्तर्गत अस्थायी पूर्णस्थापन कार्य (Motorable Work) का प्राक्कलन समर्पित करने के संबंध में।

महाशय,

उपर्युक्त विषयक सूचित करना है कि अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, दरभंगा के द्वारा आपके प्रमंडल अंतर्गत एफ0डी0आर0 योजनान्तर्गत अस्थायी पूर्णस्थापन कार्य (Motorable Work) के पथों एवं प्राक्कलन की जाँच हेतु निदेश दिया गया था। जिसके आलोक में जाँचापरांत पथ का प्राक्कलन समर्पित की जाती है। विवरणी निम्न प्रकार से है:-

RWD(W) Sub Division Singhwara			
Flood affected Road Lists for Year-2021-22			
Sr. No.	List of Eligible Roads	Flood affected length(mtr)	Restored quantity(m3)
1	L023-L022 to Dharampur (VR23)	1.550	1.550
2	T02 to Chamnpur	9.000	5.400
3	PMGSY Katasa to Gaurinath Barhmpura	233.700	91.230
4	MMGSY to Jha ji Tola	113.260	30.680
5	T02 - AGYASPUR	54.200	16.100

6	T01 - BIRDIPUR	15.500	34.410
7	N.H -57 sastri chowk sa P.W.D path	16.000	32.690
8	Govindpur PMGSY to Birdepur EDGHAH	65.500	28.750
9	P.W.D. Pak Tola to Sanhpur Via Chakauti	107.000	33.250
10	PMGSY to Kushamari Tola	122.700	15.400
11	Rasulpur PWD Rd to Saraiya	70.500	79.040
12	Darbhangha Sima to L065 Biribala Tinkonama	43.000	19.770
13	PWD Road to Ghop Tola.	30.000	11.880
14	NH 57 to Bhawara Tol	33.500	8.880
15	REO Gandhi Chauk to Birdipur Dih Tola	18.000	14.550
16	Moen Nadi Pull Rahi Toal to Damodri Pokhar	95.000	19.080
17	Reo to Karti Pokhar	76.000	49.700
18	PWD Sagir Chowk to Sahani tol sima tak	93.000	19.080
19	Pmgsy Bramhapura to Mmgsy Raghua	310.000	44.64,788.64
20	ConstrucToin of Road Bauka Chowk To asthuuaa kaligow sima Via Bhajaura Radhiya kutti	18.600	3.910
21	L033-T02 to Raghua (VR33)	88.000	14.950
22	Kora to Radhawa	109.900	27.450
23	Kalwara Road To Korapaswan Tola	55.000	8.750
24	T01 NH 57 to L029 Shekh Toli Manihas	104.000	58.240

25	L049-T02 to Shankarpur (VR49)	35.500	7.990
26	PMGSY to Mushari Tol	292.000	108.950
27	REO Road to Kusumpatti via Kanuar	254.100	87.890
28	PWD Sadhwara to Sahani Tola.	28.000	16.400
29	Hariharpur Chauk to R.E.O. Road Nimrauli	168.700	72.140
30	Simri Sighwara Road	175.000	42.420
31	Dahsil to Neem Tola	50.000	90.000
32	P.W.D Path to Hariharpur	150.600	26.930
33	Mushari Tola to L037 Bhabanipur Lorika	16.000	19.472
34	Phulthua PCC Road to Kheraj Sima	12.200	18.550
35	Katasa se Sobhan	477.500	118.470
36	L068-PMGSY to Nikasi (VR68)	80.000	17.775
37	Bhajoura PMGsy to Nista Cham Toli	104.200	29.930

अनु०:-यथोक्त ।

विश्वासभाजन

[Signature]
12/03/22

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमंडल, मधुबनी ।

Inspection Report for Flood Damage Work

Date:- 18.12.2021

Name of PIUs:- Darbhanga - 2

Name of Block/Road:- Singh wara / mmmsy to Jha Jee tola

(A) For Road:-

1 Damage Location/Chainage:- In charge - 56 M to 1326.5 M

2 Damage Length:- 113.26 meter

3 Nature of Damage:- major pot holes in road

4 Details of Restoration Works:-

(i) Material being used in Restoration Works:- Brick bats (30.68 m³)

(ii) Equipment's/Tools being used in Restoration works:- Tractor, JCB

(iii) Procedure taken up in Restoration Works:- Brick bats filling

(iv) Restored Length:- 113.26 meter

(B) For Bridge:-

1 Damage Location/Chainage:-

2 Damage Length:-

3 Nature of Damage:-

4 Details of Restoration Works:-

(i) Material being used in Restoration Works:-

(ii) Equipment's/Tools being used in Restoration works:-

(iii) Procedure taken up in Restoration Works:-

(iv) Restored Length:-

N.A

work found Satisfactory.

Signature of JE/AE/EE

Signature

(Name of Inspect)

19/12/22
J.E.

19/12/22
A.E.